

Main Roads Specification

MRS16E

Establishment and Monitoring Works

IMPORTANT INFORMATION

The requirements of this document represent Technical Policy of the department and contain Technical Standards. Compliance with the department's Technical Standards is mandatory for all applications for the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

This document will be reviewed from time to time as the need arises and in response to improvement suggestions by users. Please send your comments and suggestions to the feedback email given below.

FEEDBACK

Your feedback is welcomed. Please send to mr.techdocs@tmr.qld.gov.au.

COPYRIGHT

© State of Queensland (Department of Transport and Main Roads) 2009

Copyright protects this publication. Except for the purposes permitted by and subject to the conditions prescribed under the Copyright Act, reproduction by any means (including electronic, mechanical, photocopying, microcopying or otherwise) is prohibited without the prior written permission of the department. Enquiries regarding such permission should be directed to the Road & Delivery Performance Division, Queensland Department of Transport and Main Roads.

DISCLAIMER

This publication has been created for use in the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

Where the publication is used in other than the department's infrastructure projects, the State of Queensland and the department gives no warranties as to the completeness, accuracy or adequacy of the publication or any parts of it and accepts no responsibility or liability upon any basis whatever for anything contained in or omitted from the publication or for the consequences of the use or misuse of the publication or any parts of it.

If the publication or any part of it forms part of a written contract between the State of Queensland and a contractor, this disclaimer applies subject to the express terms of that contract.

June 09

Table of Contents

	Page
1 INTRODUCTION.....	1
2 MEASUREMENT OF WORK.....	1
2.1 Standard Work Items	1
2.2 Standard Work Items	1
2.2.1 Weed, Pest and Disease Control.....	1
2.2.2 Slashing and Brushcutting.....	2
2.2.3 Landscape and Revegetation Establishment and Monitoring	2
3 PAYMENT.....	3
3.1 Establishing and Monitoring – General.....	3
3.2 Selective Removal of Non-complying Vegetation from Seeded Areas.....	3
3.3 Method of Payment for LR Establishment and Monitoring Works – Input Controlled	3
3.4 Payment Due to Factors outside the Control of the Contractor.....	3
3.5 Method of Payment for LR Monitoring Works – Performance Based.....	3
3.6 Payment for Watering of Plant Material during LR Monitoring Period.....	4

Establishment and Monitoring Works

1 INTRODUCTION

This Specification applies to landscape and revegetation establishment and monitoring operations associated with road construction. This Specification shall be read in conjunction with MRTS16 *General Requirements*, and the Annexure and Appendix of MRTS16E.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Main Roads Specifications and Technical Standards Manual.

2 MEASUREMENT OF WORK

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the standard work items covered by this Specification are listed in Table 2.1.

Table 2.1 – Standard Work Items

Standard Work Item No.	Landscape and Revegetation Works Description	Unit of Measurement
WEED, PEST AND DISEASE CONTROL		
3728P	Weed, Pest and Disease Control Proposal – Provisional Item (if ordered).	lump sum
3729P	Mechanical herbicide application [<i>knock-down residual</i>] – Provisional Quantity (if ordered).	m ²
3730P	Manual herbicide application [<i>knock-down residual</i>]	m ²
3731P	Hand removal of weeds.	lump sum
3732P	Target herbicide application [<i>additional rate to items 3729 3730</i>].	m ²
3733P	Mechanical or manual pesticide application [<i>pesticide type</i>].	lump sum
SLASHING AND BRUSHCUTTING		
3738	Slashing.	m ²
3739	Brushcutting.	m ²
LANDSCAPE AND REVEGETATION (LR) ESTABLISHMENT AND MONITORING		
3795	LR Construction Establishment Period – Input Controlled.	lump sum
3797	LR Monitoring Period – Input Controlled.	lump sum
3798	LR Monitoring Period – Performance Based.	lump sum
3799P	Watering of plant material during LR monitoring period – Provisional (if ordered).	kilolitre

2.2 Standard Work Items

2.2.1 Weed, Pest and Disease Control

Item 3728P Weed, Pest and Disease Control Proposal – Provisional Item (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) Preparation of a Pest and Disease Control Proposal (P&DCP).

Item 3729P Mechanical herbicide application – [knock-down / residual] – Provisional Quantity (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) The mechanical application of knock-down or residual herbicide using boom spray or high volume power applicator.

Item 3730P Manual herbicide application – [knock-down / residual] – Provisional Quantity (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) The manual application of knock-down or residual herbicide from knapsack or similar applicator.

Item 3731P Hand removal of weeds – Provisional Item (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) The manual removal and disposal of weeds.

Item 3732P Target herbicide application – [additional rate to Items 3729 / 3730] – Provisional Quantity (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) The application of specific herbicides.

Item 3733P Mechanical or manual pesticide application – [pesticide type] – Provisional Item (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) The application of pesticides.

2.2.2 Slashing and Brushcutting

Item 3738 Slashing.

Item 3739 Brushcutting.

Work operations incorporated in the above items include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Work Operations incorporated in 3738 and 3739; and
- c) Cutting of grass and / or other vegetation.

2.2.3 Landscape and Revegetation Establishment and Monitoring

Item 3795 LR Construction Establishment Period – Input Controlled.

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Operations to ensure sustainability of plants; and
- c) supply and installation and re-establishment of failed landscape and revegetation plants.

Item 3797 LR Monitoring Period – Input Controlled.

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;

- b) Operations to ensure sustainability of recently installed plants;
- c) supply and installation and re-establishment of failed landscape and revegetation plants;
- d) monitoring of installations including joint inspections; and
- e) reporting.

Item 3798 LR Monitoring Period – Performance Based.

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Seeding operations;
- c) operations to ensure sustainability of recently installed plants;
- d) supply and installation and re-establishment of failed landscape and revegetation plants;
- e) monitoring of installations including joint inspections; and
- f) reporting.

Item 3799P Watering of plant material during LR Monitoring Period – Provisional Quantity (if ordered).

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*; and
- b) Watering of plant material where required, if ordered.

3 PAYMENT

3.1 Establishing and Monitoring – General

Payment for planting operations is made separate to the landscape and revegetation planting operations, under Work Items 3787 to 3789 (refer MRTS16C *Vegetation Works*).

3.2 Selective Removal of Non-complying Vegetation from Seeded Areas

No separate payment shall be made for selective removal of non-complying vegetation.

3.3 Method of Payment for LR Establishment and Monitoring Works – Input Controlled

Provided that the Contractor is fulfilling all of its obligations in the establishment and monitoring periods, payment for Items 3795 and 3797 shall be as follows –

- a) the first two progress payments shall each comprise 20% of the tendered amount;
- b) subsequent monthly progress payments shall comprise 10% of the tendered amount until total payments comprise 90% of the tendered amount; and
- c) the remaining 10% of the tendered amount is payable following the issue of the Certificate of Finalisation of the Monitoring Period (CFMP).

3.4 Payment Due to Factors outside the Control of the Contractor

The Principal will be responsible for payment of the replacement and repair of landscape and revegetation installations where damage has occurred due to factors outside the control of the Contractor, such as vehicular runoff, theft and / or vandalism.

It is the responsibility of the Contractor to do all that is reasonably practicable to minimize the risk of theft and / or vandalism of the landscape and revegetation installations.

3.5 Method of Payment for LR Monitoring Works – Performance Based

Provided that the performance of the seeded areas is consistent with the sample installation performance, payment for Item 3798 shall be as follows –

- a) the first two progress payments shall each comprise 20% of the tendered amount;

- b) subsequent monthly progress payments shall comprise 10% of the tendered amount until total payments to date comprise 90% of the tendered amount; and
- c) the remaining 10% of the tendered amount is payable following the issue of the Certificate of Finalisation of the Monitoring Period (CFMP).

3.6 *Payment for Watering of Plant Material during LR Monitoring Period*

Where the Superintendent directs the Contractor to water landscape and revegetation works during the monitoring period to prevent vegetation from becoming severely stressed in extreme weather conditions, payment shall be made at the tendered rate per kilolitre.