

Main Roads Specification

MRS16A

Vegetation Protection Works

June 09

IMPORTANT INFORMATION

The requirements of this document represent Technical Policy of the department and contain Technical Standards. Compliance with the department's Technical Standards is mandatory for all applications for the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

This document will be reviewed from time to time as the need arises and in response to improvement suggestions by users. Please send your comments and suggestions to the feedback email given below.

FEEDBACK

Your feedback is welcomed. Please send to mr.techdocs@tmr.qld.gov.au.

COPYRIGHT

© State of Queensland (Department of Transport and Main Roads) 2009

Copyright protects this publication. Except for the purposes permitted by and subject to the conditions prescribed under the Copyright Act, reproduction by any means (including electronic, mechanical, photocopying, microcopying or otherwise) is prohibited without the prior written permission of the department. Enquiries regarding such permission should be directed to the Road & Delivery Performance Division, Queensland Department of Transport and Main Roads.

DISCLAIMER

This publication has been created for use in the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

Where the publication is used in other than the department's infrastructure projects, the State of Queensland and the department gives no warranties as to the completeness, accuracy or adequacy of the publication or any parts of it and accepts no responsibility or liability upon any basis whatever for anything contained in or omitted from the publication or for the consequences of the use or misuse of the publication or any parts of it.

If the publication or any part of it forms part of a written contract between the State of Queensland and a contractor, this disclaimer applies subject to the express terms of that contract.

June 09

Table of Contents

| | Page |
|-----------------------------------|------|
| 1 INTRODUCTION..... | 1 |
| 2 MEASUREMENT OF WORK..... | 1 |
| 2.1 Standard Work Items | 1 |
| 2.2 Work Operations | 1 |
| 2.2.1 Vegetation Protection | 1 |

Vegetation Protection Works

1 INTRODUCTION

This Specification applies to landscape revegetation vegetation protection work operations associated with road construction. This Specification shall be read in conjunction with MRTS16 *General Requirements - Landscape and Revegetation Works* and Annexure MRTS16A.1.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Main Roads Specifications and Technical Standards Manual.

2 MEASUREMENT OF WORK

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the standard work items covered by the Specification are listed in Table 2.1.

Table 2.1 – Standard Work Items

| Standard Work Item No. | Landscape and Revegetation Works Description | Unit of Measurement |
|------------------------|--|---------------------|
| | VEGETATION PROTECTION | |
| 3704 | Fencing around vegetation. | m |
| 3705 | Padding of trees and boarding of drip zones. | lump sum |

2.2 Work Operations

2.2.1 Vegetation Protection

Item 3704 Fencing around vegetation.

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of materials and equipment;
- c) placement and fixing of vegetation protection;
- d) pruning of tree branches and shaping of shrub vegetation;
- e) signage of the vegetation protection zone;
- f) removal and disposal of materials at the end of the construction period; and
- g) the erection of fenced enclosures around vegetation.

Item 3705 Padding of trees and boarding of drip zones.

Work operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of materials and equipment;
- c) placement and fixing of vegetation protection;
- d) pruning of tree branches and shaping of shrub vegetation;
- e) signage of the vegetation protection zone;
- f) removal and disposal of materials at the end of the construction period; and
- g) the installation of padding and boarding around trees.