

# Main Roads Specification

## **MRS63**

### **Cast-In-Place Piles**

## **TRADEMARKS ACKNOWLEDGEMENT**

Terms mentioned in this document that are known or understood to be trademarks, whether registered or not, have been identified. Where trademarks have been confirmed as registered in Australia, this has been indicated by the addition of the ® symbol, otherwise the ™ symbol is used. While all care has been taken to identify trademarks, users should rely on their own inquiries to determine trademark ownership. Use of a term in this document as a trademark should not be regarded as affecting the validity of any trademark.

## **IMPORTANT INFORMATION**

The requirements of this document represent Technical Policy of the department and contain Technical Standards. Compliance with the department's Technical Standards is mandatory for all applications for the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

This document will be reviewed from time to time as the need arises and in response to improvement suggestions by users. Please send your comments and suggestions to the feedback email given below.

## **FEEDBACK**

Your feedback is welcomed. Please send to [mr.techdocs@tmr.qld.gov.au](mailto:mr.techdocs@tmr.qld.gov.au).

## **DISCLAIMER**

This publication has been created for use in the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

Where the publication is used in other than the department's infrastructure projects, the State of Queensland and the department gives no warranties as to the completeness, accuracy or adequacy of the publication or any parts of it and accepts no responsibility or liability upon any basis whatever for anything contained in or omitted from the publication or for the consequences of the use or misuse of the publication or any parts of it.

If the publication or any part of it forms part of a written contract between the State of Queensland and a contractor, this disclaimer applies subject to the express terms of that contract.

## **COPYRIGHT**

Copyright protects this publication. Except for the purposes permitted by and subject to the conditions prescribed under the Copyright Act, reproduction by any means (including electronic, mechanical, photocopying, microcopying or otherwise) is prohibited without the prior written permission of the department. Enquiries regarding such permission should be directed to the Pavements, Materials, Geotechnical and Standards Division, Queensland Department of Transport and Main Roads.

© State of Queensland (Department of Transport and Main Roads) 2010



<http://creativecommons.org/licences/by-nc-nd/2.5/au>

# Table of Contents

	Page
1 INTRODUCTION.....	1
2 MEASUREMENT OF WORK.....	1
2.1 Standard Work Items .....	1
2.2 Work Operations .....	1
2.3 Calculation of Quantities .....	4
2.3.1 Natural Ground Surface Level .....	4
2.3.2 Supply of Liners .....	4
2.3.3 Sinking or Driving of Liners.....	4
2.3.4 Excavation .....	5
2.3.5 Drilling of Test Holes.....	5
2.3.6 Concrete .....	5
2.3.7 Steel Reinforcing Bars .....	5
2.4 Assessment of Foundation Information .....	5
2.5 Socket Extension Costs .....	6



# Cast-In-Place Piles

## 1 INTRODUCTION

This Specification applies to the construction of cast-in-place, reinforced concrete piles contained in open-ended liners left permanently in place extending to competent rock or hard stratum (referred to as lined piles) for bridges.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Main Roads Specifications and Technical Standards Manual.

## 2 MEASUREMENT OF WORK

### 2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the Standard Work Items incorporated in this specification are listed in Table 2.1.

**Table 2.1 – Standard Work Items**

Standard Item No.	Description	Unit of Measurement
<b>Cast-In-Place Piles</b>		
7401	Reinforced concrete pipe liners, supply on Site [ <i>diameter</i> ].	m
7402	Handling and pitching of reinforced concrete pipe liners.	each
7403P	Sinking reinforced concrete pipe liners (Provisional Quantity).	m
7404	Steel pipe liners, supply on Site [ <i>diameter</i> ].	m
7405	Supply and fixing of stiffening bands.	each
7406	Handling and pitching of steel liners.	each
7407P	Driving steel liners (Provisional Quantity).	m
7408P	Extension of steel liners (Provisional Quantity).	m
7411P	Excavation of liners (Provisional Quantity).	m <sup>3</sup>
7412P	Excavation below toes of liners (Provisional Quantity).	m <sup>3</sup>
7413P	Excavation to form bell enlargements below liners (Provisional Quantity)	m <sup>3</sup>
7414P	Drilling of test holes (Provisional Quantity).	m
7415	Certification of pile capacity.	each
7421P	Concrete Class [ <i>Class &amp; compressive strength</i> ] MPa/20 in abutment lined pile (Provisional Quantity).	m <sup>3</sup>
7422P	Concrete Class [ <i>Class &amp; compressive strength</i> ] MPa/20 in pier lined pile (Provisional Quantity).	m <sup>3</sup>
7425P	Steel reinforcing bar in piles (Provisional Quantity).	tonne

### 2.2 Work Operations

#### Item 7401 Reinforced concrete pipe liners, supply on Site [*diameter*].

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of liners, including any additional length to suit construction methods;

- c) Transport of liners to Site;
- d) Preparation of Site storage area;
- e) Storage of liners at Site; and
- f) Additional length, if any, required to suit the Contractor's proposed construction method.

**Item 7402 Handling and pitching of reinforced concrete pipe liners.**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Transferring liner from on Site storage to its aligned position; and
- c) Temporary connections and/or bracing to safely restrain segments of pile shaft.

**Item 7403P Sinking reinforced concrete pipe liners (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Preboring of hole(s) for liner
- c) Lowering and/or assisting liner into excavation or pre-bored holes;
- d) Supporting toe of liner at all times; and
- e) Trimming the liner to level on completion.

**Item 7404 Steel liners, supply on Site, [diameter].**

Work Operations incorporated in the above items include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of liners, including any additional length to suit construction methods;
- c) Transport of liners to Site;
- d) Preparation of Site storage area;
- e) Storage of liners at Site; and
- f) Additional length, if any, required to suit the Contractor's proposed construction method.

**Item 7405 Supply and fixing of stiffening bands.**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of stiffening bands; and
- c) Fixing stiffening bands to liner, as per the Drawings.

**Item 7406 Handling and pitching of steel liners.**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Transferring liner from on Site storage to its aligned position in the driving rig;
- c) Provision and use of driving rig; and
- d) Retention of liner on line for driving.

**Item 7407P Driving steel liners (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Any preboring shown on the drawings or approved by the Superintendent, including filling the gap between liner and excavated hole with flowable fill or approved alternative;

- c) Driving the liner;
- d) Field splices made during driving;
- e) Trimming the liner to level on completion;
- f) Setting up to re-drive liners, where liners are driven in increments with progressive excavation;
- g) Re-driving of liners to achieve a seal;
- h) Repair of any damage to liner necessary to complete construction; and
- i) Driving of extended steel liner.

**Item 7408P Extension of steel liners (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Preparation for welding; and
- c) Full penetration butt welding of liners.

**Item 7411P Excavation of liners (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Excavation of material;
- c) Disposal of excavated material;
- d) De-watering;
- e) Sealing the toe of liners against entry of water or material;
- f) Interruptions where liners are driven in increments with progressive excavation; and
- g) The provision on site and use of any special equipment to safely inspect and clean pile holes.

**Item 7412P Excavation below toes of liners (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Excavation of material;
- c) Disposal of excavated material;
- d) De-watering; and
- e) Provision of safe access for inspection, including safety shield, if required.

**Item 7413 Excavation to form bell enlargements below liners.**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Excavation of material;
- c) Disposal of excavated material;
- d) De-watering; and
- e) Provision of safety shield, if required.

**Item 7414P Drilling of test holes (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Provision of safe access for drilling, including safety shield, if required; and
- c) Drilling of test holes and the recording of drill time and depth.

**Item 7415 Certification of pile capacity.**

Work Operations incorporated in the above item include –

- d) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- e) Assessment of information including information available to Tenderers;
- f) Undertaking additional investigations and reporting of investigations;
- g) Provision of safe access for inspection, including safety shield, if required;
- h) Inspection and logging of the foundation by the Contractor's Geotechnical Assessor;
- i) Geotechnical certification of foundation capacity; and
- j) Provision of "as-constructed" records.

**Item 7421P Concrete Class [Class and compressive strength] MPa/20 in abutment lined pile (Provisional Quantity).**

**Item 7422P Concrete Class [Class and compressive strength] MPa/20 in pier lined pile (Provisional Quantity).**

Work Operations incorporated in the above items include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of concrete;
- c) Transport of concrete;
- d) Placing and compacting concrete; including the provision of a tremie and all necessary equipment for placing concrete underwater, if the hole is not dry;
- e) Finishing and curing concrete; and
- f) Removal of any nonconforming concrete at the top of the pile and replacement if necessary.

**Item 7425P Steel reinforcing bar in piles (Provisional Quantity).**

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of all materials, including any additional steel required to form a pile cage that can be safely lifted and placed into the pile shaft;
- c) Fixing reinforcing steel in place; and
- d) The provision of stainless steel nibs or approved spacers to maintain minimum specified concrete cover.

**2.3 Calculation of Quantities**

**2.3.1 Natural Ground Surface Level**

The natural ground surface level shall be taken as the level determined from the contours shown on the Drawings unless agreed otherwise, in writing, by the Contractor and Administrator, prior to commencing excavation.

**2.3.2 Supply of Liners**

Supply of liners of the nominated thickness shall be the length of liner shown on the Drawings which includes an allowance for possible variations in foundation levels. Prior to ordering the liners, the Contractor shall check that the supply length is adequate for the proposed construction methods such as extending the liners above high tide level in tidal waters.

**2.3.3 Sinking or Driving of Liners**

Sinking or driving of liners shall be the length of liner, in place, measured along the pile axis from the toe of the liner to the approved top cut-off level, or to the natural ground surface level, whichever is the lower.

## 2.3.4 Excavation

### 2.3.4.1 General

The volume stated in the Schedule of Rates against any Work Item for excavation is the aggregate excavation from all areas and for all materials as stated in Clause 5 of MRTS63.

Over excavation shall not be included in the Measurement of Work under any Work Item. Over-excavation includes both increased diameter and non-approved deepening of the excavation, or deepening to suit the Contractors work methods.

### 2.3.4.2 Excavation of Liners

Excavation of liners shall be measured as the volume calculated from the approved toe (that is, terminal level) of the liner to the natural ground surface level, or to the underside of the pile cap or headstock if that is lower, using the nominal internal diameter of liner shown on the Drawings.

### 2.3.4.3 Excavation below Toe of Liner (Excluding Bell Enlargement)

Excavation below the toe (that is, terminal level) of the liner shall be measured as the volume of the cylinder of material whose diameter is equal to the inside diameter of the liner and whose length is measured from the base of the excavation up to the terminal level of the liner. Any additional excavation to extend the socket length, where design skin friction is downgraded due to failure to obtain a water tight seal and allow proper inspection and assessment, shall not be included in quantities for payment.

### 2.3.4.4 Excavation to Form Bell Enlargement

The additional excavation required to form a bell or other enlargement outside the plan profile of the main cylindrical shaft shall be measured as the volume of material excavated outside that measured under Clause 2.3.4.3, as is necessary to form bells or other enlargements to the dimensions determined in accordance with MRTS63.

## 2.3.5 Drilling of Test Holes

Drilling of test holes shall be measured as the length of hole drilled below the bottom of the excavation as ordered in accordance with Clause 11.6.4 of MRTS63.

## 2.3.6 Concrete

For lined piles, the quantity of concrete shall be calculated as the sum of –

- a) the volume calculated from the approved terminal level of the liner to the underside of the pile cap, headstock or other specified level shown on the Drawings using the nominal internal diameter of liner shown on the Drawings; and
- b) the quantities determined in accordance with Clauses 2.3.4.3 and 2.3.4.4.

Deductions will not be made for the volume occupied by reinforcing steel.

No measurement will be made for concrete required to fill over-break in excavation.

## 2.3.7 Steel Reinforcing Bars

The quantity of steel reinforcing bars shall be calculated in accordance with Clause 2.3 of MRS71 *Reinforcing Steel*. The quantity shall be increased where appropriate to include additional steel reinforcing bars required by extensions to the length of piles.

## 2.4 Assessment of Foundation Information

In the schedule, where any item for foundation work is inclusive of work from a number of discrete areas, the aggregate quantity shown for that item encompasses a range of constituent materials having similar physical properties and similar overall relative proportions of the different components as could be expected from information provided in the Tender Documents. The actual disposition and volumes of the various constituent materials within any individual pile may vary somewhat from those indicated by adjacent boreholes, but no additional compensation shall be paid where the aggregate quantities of the various components for all locations scheduled under the item are compatible with those indicated in the Tender Documents

## **2.5    *Socket Extension Costs***

Any socket extensions necessitated by Clauses 11.10.2 and 11.10.3 in Technical Standard MRTS63, including all consequential costs and delays, shall be at no cost to the Principal.