Specification (Measurement)

Transport and Main Roads Specifications MRS96 Management and Removal of Asbestos

July 2017



Copyright



http://creativecommons.org/licenses/by/3.0/au/

© State of Queensland (Department of Transport and Main Roads) 2017

Feedback: Please send your feedback regarding this document to: tmr.techdocs@tmr.qld.gov.au

Contents

1	Introduction	
2	Measurement of Work	1
2.1	Standard Work Items	. 1
2.2	Work Operations	. 1
2.3	Rate of Payment for Item 21301	. 2

1 Introduction

This Specification applies to the management and safe removal of asbestos from existing transport infrastructure including:

- bridges (for example, rehabilitation works including widening, strengthening and damage due to vehicle impact)
- · electrical conduits and pits
- water mains, sewer mains and drainage pipes, and
- miscellaneous products.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Transport and Main Roads Specifications Manual.

2 Measurement of Work

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the Standard Work Items incorporated in this Specification are listed in Table 2.1.

Table 2.1 – Standard Work Items

Standard Item No.	Description	Unit of Measurement
	Managing and Removing Asbestos	
21301	Identifying and managing asbestos on Site [description]	lump sum
21302	Removing and disposing of Asbestos Containing Material on Site [description]	lump sum

2.2 Work Operations

Item 21301 Identifying and managing asbestos on Site [description]

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 Introduction to Specifications
- b) all activities associated with the identification and management of asbestos on the Site, and
- c) supply of all documentation including updated asbestos register.

Item 21302 Removing and disposing Asbestos Containing Material on Site [description]

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 Introduction to Specifications
- b) supply and transport of all personnel, plant, equipment and materials to and from the Site
- c) obtaining all necessary licenses and permits under relevant legislation
- d) removal of all Asbestos Containing Material as shown in the Contract

- e) safe disposal of Asbestos Containing Material in accordance with WHS requirements, and
- f) supply of all documentation including certificates and registers.

2.3 Rate of Payment for Item 21301

Payment for Item 21301 will be made by the Principal in three stages in accordance with the provisions of this clause.

Provided the Contractor is fulfilling all its obligations under the Contract, one-third of the Lump Sum amount will be included in the Payment Certificate at the end of the month when one third of the total work on Site (including rehabilitation works) has been completed. The next two components will be included in the Payment Certificate at the end of the month on completion of each portion of total work.