

**Technical Specification** 

# **Transport and Main Roads Specifications MRTS204 Vehicle Detectors**

November 2020



# Copyright

© The State of Queensland (Department of Transport and Main Roads) 2020.

#### Licence



This work is licensed by the State of Queensland (Department of Transport and Main Roads) under a Creative Commons Attribution (CC BY) 4.0 International licence.

### CC BY licence summary statement

In essence, you are free to copy, communicate and adapt this work, as long as you attribute the work to the State of Queensland (Department of Transport and Main Roads). To view a copy of this licence, visit: <u>https://creativecommons.org/licenses/by/4.0/</u>

#### Translating and interpreting assistance



The Queensland Government is committed to providing accessible services to Queenslanders from all cultural and linguistic backgrounds. If you have difficulty understanding this publication and need a translator, please call the Translating and Interpreting Service (TIS National) on 13 14 50 and ask them to telephone the Queensland Department of Transport and Main Roads on 13 74 68.

#### **Disclaime**r

While every care has been taken in preparing this publication, the State of Queensland accepts no responsibility for decisions or actions taken as a result of any data, information, statement or advice, expressed or implied, contained within. To the best of our knowledge, the content was correct at the time of publishing.

#### Feedback

Please send your feedback regarding this document to: tmr.techdocs@tmr.qld.gov.au

# Contents

| 1    | Introduction   | 1      |
|------|--|--------|
| 2    | Definition of terms                                    | 1      |
| 3    | Referenced documents                                   | 3      |
| 4    | Quality system requirements                            | 4      |
| 4.1  | Hold Points and Witness Points                         | 4      |
| 4.2  | Samples for evaluation and product type approval       | 5      |
| 4.3  | Plans for Site acceptance testing and certification    | 5<br>5 |
| 4.4  | Warranty   | 5      |
| 4.5  | Documentation submitted prior to commencement of Works | 5      |
| 5    | Functional requirements                                | 6      |
| 6    | Operational requirements                               | 7      |
| 7    | Performance requirements                               | 7      |
| 8    | Mechanical and physical requirements                   | 7      |
| 9    | Design requirements                                    | .8     |
| 10   | Electrical requirements                                | .8     |
| 10.1 | Lightning / surge protection                           | 8      |
| 11   | Telecommunication requirements                         | 8      |
| 11.1 | STREAMS compatibility                                  | 9      |
| 11.2 | Communication  | 9      |
| 12   | Electromagnetic compatibility                          | 9      |
| 13   | Installation requirements                              | 9      |
| 14   | Testing and commissioning                              | 0      |
| 15   | Documentation  | 0      |
| 16   | Training   | 0      |
| 17   | Handover   | 0      |
| 18   | Maintenance 1  | 1      |
| Арре | endix A - Loop detectors                               | 2      |
| A1   | General1   | 2      |
| A2   | Equipment components                                   | 2      |
| A3   | Operational requirements                               | 2      |
| A3.1 | Operating modes  | 3      |
| A3.2 | Length of detector feeder cable                        | 3      |
| A3.3 | Inductance range and frequency1                        | 3      |
| A3.4 | Actuation range1                                       | 3      |
| A3.5 | Sensitivity settings                                   | 3      |
| A3.6 | Turn-off time  | 3      |

| A3.7       | Presence time   | 13 |
|------------|---|----|
| A3.8       | Automatic drift compensation (tracking)               | 13 |
| A3.9       | Recovery from positive inductance change              | 14 |
| A3.1       | 0 Susceptibility to interference                      | 14 |
| A3.1       | 1 Crosstalk   | 14 |
| A3.12      | 2 Leakage to earth                                    | 14 |
| A4         | Mechanical and physical requirements                  | 14 |
| A4.1       | Detector card dimensions                              | 14 |
| A4.2       | Indicators  | 14 |
| A4.3       | Switches and adjustment facilities                    | 14 |
| A4.4       | Connection facility                                   | 14 |
| A5         | Electrical requirements                               | 14 |
| A6         | Installation requirements                             | 14 |
| A6.1       | Commencement of Works                                 | 15 |
| A6.2       | Loop configuration and loop spacing                   | 15 |
| A6.3       | Installation of vehicle detector loops                | 15 |
| A6.4       | Installation of feeder cables                         | 16 |
| A6.5       | Loop feeder terminal panel                            | 16 |
| <b>A</b> 7 | Communication   | 16 |
| <b>A</b> 8 | Testing and Commissioning                             | 16 |
| A8.1       | General   | 16 |
| A8.2       | Testing equipment requirements                        | 17 |
| A8.3       | Testing of feeder cable                               | 17 |
| A8.4       | Testing of individual loop                            | 17 |
| A8.5       | Testing of loop cable and feeder cable circuit        | 18 |
| A8.6       | Testing during installation                           | 18 |
| Арре       | endix B - Infrared Vehicle Detectors                  | 19 |
| B1         | General   | 19 |
| B2         | Equipment components                                  | 19 |
| B3         | Functional requirements                               | 19 |
| B4         | Operational requirements                              | 19 |
| B5         | Power   | 20 |
| B5.1       | Modulation  | 20 |
| B5.2       | Misalignment  | 20 |
| B5.3       | Transmitter power and receiver sensitivity adjustment | 20 |
| <b>B6</b>  | Mechanical and physical requirements                  | 20 |
| B7         | Electrical requirements                               | 20 |
| <b>B</b> 8 | Electromagnetic compatibility / safety approval       | 20 |
| B9         | Installation requirements                             | 20 |

| B10  | Testing and commissioning                             | 21 |
|------|---|----|
| Арре | endix C - Radar Vehicle Detectors                     | 22 |
| C1   | General   | 22 |
| C2   | Equipment components                                  | 22 |
| C3   | Functional requirements                               | 22 |
| C4   | Operational requirements                              | 22 |
| C4.1 | Frequency   | 22 |
| C4.2 | Side lobes  | 22 |
| C4.3 | Bandwidth   | 23 |
| C4.4 | Transmitter power and receiver sensitivity adjustment | 23 |
| C4.5 | Beamwidth stability                                   | 23 |
| C4.6 | Frequency channels                                    | 23 |
| C5   | Mechanical and physical requirements                  | 23 |
| C6   | Performance requirements                              | 23 |
| C7   | Electrical requirements                               | 23 |
| C8   | Installation requirements                             | 24 |
| C9   | Testing of Radar Vehicle Detector                     | 24 |
| Арре | endix D - Form M4300                                  | 25 |
|      |   |    |

# 1 Introduction

This Technical Specification defines the design, supply, installation, testing and commissioning, functional, performance, documentation, training and maintenance requirements of vehicle detectors. This document applies to the following types of vehicle detectors:

- Loop Detectors
- Radar Vehicle Detectors, and
- Infrared Vehicle Detectors.

The scope of this Technical Specification includes the following:

- design of the site-specific system
- supply and installation of the above indicated vehicle detectors together with necessary accessories
- supply and installation of the associated structures
- electrical switchboard and associated internal wiring compliant with MRTS228 Electrical Switchboards
- provision and connection of mains power compliant with MRTS210 Provision of Mains Power
- communications between vehicle detectors and field processor, and
- connection to the Transport and Main Roads telecommunications network as per MRTS232 Provision of Field Processors and MRTS245 ITS Telecommunications Network (ITS TN).

The general requirements of all type of vehicle detectors are listed in the amin body of this Technical Specification. Specific requirements relating to each type of detectors is listed in the appendices.

The requirements of traffic counter / classifier and pedestrian / cyclist counters are not within the scope of this document and reference should be made to MRTS251 *Traffic Counter/Classifier* for specific requirements of traffic counter and classifier.

This Technical Specification shall be read in conjunction with MRTS01 *Introduction to Technical Specifications*, MRTS50 *Specific Quality System Requirements*, MRTS201 *General Equipment Requirements* and other Technical Specifications as appropriate.

This Technical Specification forms part of the Transport and Main Roads Specifications Manual.

# 2 Definition of terms

The terms defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification. Additional terminology relevant to this Technical Specification is defined in Table 2.

### Table 2 – Definitions

| Term              | Definition  |
|-------------------|---|
| ARRB              | Australian Road Research Board  |
| CAT               | Customer Acceptance Test  |
| CDO               | Camera-Detected Offences  |
| Detector          | A device by which the presence and / or passage of vehicles or pedestrians is registered  |
| Detector loop     | One or more loops of wire embedded into the road surface and used to detect vehicle   |
| ELV               | Extra Low Voltage as defined by AS/NZS 3000   |
| EMC               | Electromagnetic Compatibility   |
| EMI               | Electromagnetic Interference  |
| GUI               | Graphical User Interface  |
| Headway           | Time gap between successive vehicles in a traffic stream (measured at the same point on the two vehicles)                                       |
| HV                | High Voltage as defined by AS/NZS 3000  |
| IRVD              | Infrared Vehicle Detector   |
| ISM               | Industrial Scientific Medical, allocated radio frequency bands  |
| LED               | Light Emitting Diode  |
| LV                | Low Voltage as defined by AS/NZS 3000   |
| MRTS              | Transport and Main Roads Technical Specification  |
| MTBF              | Mean Time Between Failures  |
| NTP               | Network Time Protocol   |
| Occupancy         | Proportion of time that a designated point in a traffic lane is covered by vehicles   |
| PER               | Packet Error Rate   |
| PHCS              | Product Host Control System, consisting of a device that runs<br>manufacturer software to permit equipment configuration and viewing<br>of data |
| PoE               | Power over Ethernet, standardised ELV power distribution via<br>communications cables and connectors  |
| RF                | Radio Frequency   |
| RPEQ              | Registered Professional Engineer of Queensland as defined by the <i>Professional Engineers Act</i> of Queensland                                |
| RVD               | Radar Vehicle Detector  |
| SNR               | Signal-to-Noise Ratio   |
| Traffic flow data | Data describing traffic speed, volume, occupancy, headway and classification  |
| Traffic speed     | As per ARRB glossary of terms   |
| TRUM              | Traffic and Road Use Manual published by Transport and Main Roads   |
| TSC               | Traffic Signal Controller   |

| Term           | Definition   |
|----------------|--|
| VAC            | Volts alternating current                                      |
| VD             | Vehicle Detector   |
| Vehicle length | Length of discrete vehicles measured in metres                 |
| Vehicle speed  | Velocity of discrete vehicles in km/h                          |
| Vehicle volume | The number of discrete vehicles passing over a sensor per hour |
| Wiring Rules   | AS/NZS 3000  |

# 3 Referenced documents

The requirements of the referenced documents listed in Table 3 of MRTS201 *General Equipment Requirements* and Table 3 below, apply to this Technical Specification. Where there are inconsistencies between this Technical Specification and the referenced MRTS (including those referenced in MRTS201 *General Equipment Requirements*), the requirements specified in this Technical Specification shall take precedence.

#### Table 3 – Referenced documents

| Reference        | Title  |
|------------------|--|
| AS 2703          | Vehicle loop detector sensors  |
| AS 60529         | Degrees of protection provided by enclosures (IP Code)   |
| AS/NZS 1768      | Lightning protection   |
| AS/NZS 2276.2    | Cables for traffic signal installations – Feeder cable for vehicle detectors   |
| AS/NZS 3000      | Electrical installations - building structure and premises (wiring rules)  |
| AS/NZS 3100      | Approval and test – General requirements for electrical equipment  |
| AS/NZS 60950.1   | Information technology equipment - Safety Part 1: General requirements (IEC 60950-1, Ed. 2.2 (2013), MOD)  |
| AS/NZS 61000.6.1 | Electromagnetic compatibility (EMC) – Generic standards – Immunity<br>for residential, commercial and light-industrial environments                                    |
| AS/NZS 61000.6.3 | Electromagnetic compatibility (EMC)  |
| AS/NZS 61558     | Safety of transformers, reactors, power supply units and combinations thereof, Part 1: General requirements and tests (IEC 61558-1 Ed 3, MOD)                          |
| AS/NZS CISPR 11  | Industrial, scientific and medical equipment - Radio-frequency<br>disturbance characteristics - Limits and methods of measurement<br>(CISPR 11:2015+AMD1:2016 (ED.6.1) |
| Form M4300       | Vehicle Detector Loop Settings and Measurements Record   |
| MRTS01           | Introduction to Technical Specifications   |
| MRTS50           | Specific Quality System Requirements   |
| MRTS51           | Environmental Management   |
| MRTS93           | Traffic Signals  |
| MRTS201          | General Equipment Requirements   |
| MRTS210          | Provision of Mains Power   |

| Reference             | Title   |
|-----------------------|---|
| MRTS226               | Telecommunication Field Cabinets  |
| MRTS228               | Electrical Switchboards   |
| MRTS232               | Provision of Field Processors   |
| MRTS245               | ITS Telecommunications Network (ITS TN)   |
| MRTS251               | Traffic Counter/Classifier  |
| MRTS257               | Feeder Cable and Loop Cable for Vehicle Detector  |
| Standard Drawing 1424 | Traffic signals - Detector loops installation details                                   |
| Standard Drawing 1425 | Traffic signals - Detector loops placement details                                      |
| Standard Drawing 1426 | Traffic signals – Detector loops standard configuration                                 |
| Standard Drawing 1701 | Traffic Signals - Detector loops counting/right turn loops and diode connection details |
| Standard Drawing 1702 | ITS - Detector loops motorway management placement details                              |
| TRUM Vol 4 Part 5     | Configuration and Placement of Vehicle Detection Sensors                                |

# 4 Quality system requirements

The quality system requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification.

### 4.1 Hold Points and Witness Points

General requirements for Hold Points, Witness Points and Milestones are specified in Clause 5.2 of MRTS01 *Introduction to Technical Specifications*.

The Hold Points and Witness Points applicable to this Technical Specification are summarised in Table 4.1. There are no Milestones defined.

| Table 4.1 – | Hold | Points | and | Witness | Point | ts |
|-------------|------|--------|-----|---------|-------|----|
|             |      |        |     |         |       |    |

| Clause             | Hold Point  | Witness Point                     | Milestone |
|--------------------|---|-----------------------------------|-----------|
| 4.3                | 1. Plans for site acceptance testing and certification          |                                   |           |
| 4.5                | 2. Documentation submitted<br>prior to commencement<br>of works |                                   |           |
| 13                 | 3. Installation requirements                                    |                                   |           |
| 15                 | 4. Documentation  | 1. Documentation                  |           |
| Appendix A<br>A3.3 |   | 2. Inductance range and frequency |           |
| Appendix A<br>A6.1 | 5. Commencement of works  |                                   |           |
| Appendix A<br>A6.2 | 6. Loop configuration and loop spacing                          |                                   |           |
| Appendix A<br>A8.2 |   | 3. Testing equipment requirements |           |
| Appendix A         |   | 4. Loop measurement               |           |

| Clause             | Hold Point                              | Witness Point                           | Milestone |
|--------------------|---|---|-----------|
| A8.4               |   | records                                 |           |
| Appendix A<br>A8.5 |   | 5. Loop measurement records             |           |
| Appendix B<br>B10  | 7. Testing and commissioning            | 6. Testing and commissioning            |           |
| Appendix C<br>C9   | 8. Testing of Radar Vehicle<br>Detector | 7. Testing of Radar Vehicle<br>Detector |           |

# 4.2 Samples for evaluation and product type approval

The Contractor shall make available for approval by the Principal / Administrator a sample of either a complete vehicle detecting system, or materials intended for the construction of the device at least 14 days prior to planned commencement of fabrication.

# 4.3 Plans for Site acceptance testing and certification

The Contractor shall supply site acceptance test plans to the Superintendent for approval 28 days prior to the site acceptance start date. Hold Point 1

The site acceptance test for the installed equipment shall be included in a report together with handover documents as per MRTS201 *General Equipment Requirements* to the Superintendent for approval prior to the date of practical completion.

All non-conformances identified during the site acceptance testing shall be rectified at no cost to the Principal.

# 4.3.1 Product type approval

Only those products that have been type approved by ITS Technologies unit of Transport and Main Roads shall be installed on the road network.

# 4.4 Warranty

Warranty requirements of MRTS201 *General Equipment Requirements* shall apply, additional requirements are as follows.

The Contractor shall guarantee the equipment system supplied for a period of 24 months after the completion of Customer Acceptance Test (CAT). The component parts shall each have a warranty of at least two years from the date of handover and at least five years for any part that is battery powered.

# 4.5 Documentation submitted prior to commencement of Works

Prior to the commencement of Works, the successful tender will provide to the Principal for approval and retention, three electronic copies of:

- fabrication and assembly drawings that include all of the components
- manufacturer's specifications (catalogue extracts) of all major components detailing ratings and performance characteristics of the same
- a schematic layout of components, building details and interconnection diagrams

- the Quality Assurance system in compliance with MRTS50 *Specific Quality System Requirements* within 14 calendar days of the Letter of Acceptance unless specified otherwise in contract, and
- contractors compliance with MRTS51 Environmental Management.

# Hold Point 2

# 5 Functional requirements

The vehicle detection system shall provide at least the following data:

- vehicle volume
- lane occupancy
- vehicle speed
- per direction average speed
- per lane average speed, and
- headway data.

Vehicle detectors are also used for camera-detected offences.

In the case of vehicle detector loops, electrical cables connect the point of detection (loop) to the detector module. This is not the same for other types of detectors. The requirements on system communications are different for different types of detectors.

The vehicle detection system shall be able to communicate real-time data to the Principal's traffic management system (STREAMS) via a field processor and Principal's telecommunication system as per the provisions in MRTS232 *Provisions of Field Processors* and MRTS245 *ITS Telecommunications Network (ITS TN)*.

The vehicle detection system shall consist of an internal clock. Facilities shall be available for the date and time of the internal clock to be set via the field processor to synchronise with NTP. All data shall consist of time details.

Each vehicle detector system shall be able to automatically re-tune / reset at the power on or detection of abnormality and load the site-specific configurations. It is also necessary to have local and remote reset facilities. When the detector system automatically re-tune / reset, it must advise the field processor of the start and end of the automatic re-tuning process.

The vehicle detection system shall have facility to store data within the system in non-volatile memory up to five million detections. In case of loss of communication with the traffic management system, data during the period of communication lost shall be automatically uploaded to the traffic management system once communication is resumed. Type of the data to be uploaded shall be user configurable. The data stored within the vehicle detection system shall be accessible through the Principal's telecommunication network.

The above functional requirements are common to all vehicle detectors, except for those used for camera-detected offences. Functional requirements pertaining to specific kinds of vehicle detectors are listed in the appendices.

# 6 Operational requirements

The operational requirements defined in MRTS201 *General Equipment Requirements* are applicable to this Technical Specification.

The vehicle detection system shall have Windows®-based Graphic User Interface (GUI) for viewing real-time data and stored data. GUI shall be able to operate on all versions of Windows current at the time of procurement of the vehicle detection system. Viewing options shall be user-configurable. The GUI shall be able to run in both the traffic management system and PHCS. GUI shall have facility to display traffic history pattern at least for the last 1.5 sec together with current traffic data.

The firmware shall be upgradable through any communication port remotely using the Principal's telecommunication network or local connection at the site.

The vehicle detection system shall be reliable (MTBF greater than 10 years at 95% confidence level), low maintenance (minimum maintenance period greater than one year) and operate in all environmental conditions specified in MRTS201 *General Equipment Requirements*.

System-specific operational requirements are listed in the appendices.

# 7 Performance requirements

The vehicle detection data shall have the following accuracies / performance parameters when individual vehicle speeds are between 20 km/hr and 110 km/hr and traffic flow up to 2400 vehicles/hr/lane, excluding vehicle detectors used for camera-detected offences:

- vehicle speed 5 km/hr
- per direction average speed 95% averaged over 15 minutes
- per lane average speed 95% averaged over 15 minutes
- vehicle volume 98% averaged over 15 minutes
- lane occupancy 98% averaged over 15 minutes
- headway data 98%, and
- detection finalisation time < 80 ms.

The detection system and associated structure shall be able to operate in environmental conditions listed in MRTS201 *General Equipment Requirements* and variation in operating conditions specified in AS 2703 *Vehicle loop detector sensors*. The vehicle detection system shall be able to operate in all weather conditions including rain up to 100 mm per hour. All system components shall have at least 20 years life span.

The detection system shall automatically start to operate within 10 seconds of power up or interruption of power.

Further performance requirements pertaining to specific types of vehicle detectors are listed in the appendices.

# 8 Mechanical and physical requirements

The mechanical and physical requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification. All pavement-mounted hardware shall withstand vibration of repeated pavement impacts from up to 50,000 vehicles per day.

All power supply units and other additional hardware that are required to be installed in the field cabinet shall be mountable in 19-inch rack and meet the provisions of MRTS226 *Telecommunication Field Cabinets*.

Further mechanical and physical requirements pertaining to specific kinds of vehicle detectors are listed in the appendices.

# 9 Design requirements

Detail design drawings, design calculations, manufacturer Specifications and schematic layout of the components shall be forwarded to the Principal for review. All designs shall be certified by a suitably qualified RPEQ.

Vehicle detectors associated with Camera-Detected Offences (CDO) shall have detail design drawings, design calculations, specifications and schematic layout of the relevant components shall be forwarded to the Photographic Detection Device (PDD) Manufacturer for review and certification by an appropriately qualified RPEQ prior to installation.

# **10 Electrical requirements**

The electrical requirements defined in MRTS201 *General Equipment Requirements* and MRTS228 *Electrical Switchboards* apply to this Technical Specification. Main power shall be provided at each site in accordance with the provisions in MRTS210 *Provision of Mains Power*. All electrical work shall be in accordance with the Electrical Legislation, AS/NZS 3000 *Wiring Rules* and AS/NZS 3100 *Approval and test – General requirements for electrical equipment*.

Additional electrical requirements under this Technical Specification are as follows:

- Unless otherwise specified, power supply to the vehicle detector system shall be 230 VAC +/- 10%. Power converters shall be used to obtain other power requirements.
- The mains power supply input shall be fused and isolated. The output from the LV power supply shall be protected against short circuit conditions and provide overload protection. All fault conditions shall be cleared by an electrical protection device in less than 400 ms in compliance with AS/NZS 3000 and MRTS228, and
- A main power switch shall be located on the front faceplate and illuminated to indicate the availability of mains power and LEDs shall be located on the power supply front faceplate to indicate available regulated output voltages.

Further electrical requirements pertaining to specific kinds of vehicle detectors are listed in the appendices.

# 10.1 Lightning / surge protection

Lightning / surge protection shall be provided to all power supply and communication cables into the field cabinet and equipment in order to mitigate effect from voltage transient in accordance with provisions in AS/NZS 1768 *Lightning protection*.

# **11** Telecommunication requirements

Each vehicle detection site, excluding vehicle detectors used for Camera-Detected Offences, shall be provided with telecommunication port through the Principal's telecommunication network in accordance with provisions in MRTS245 *ITS Telecommunications Network (ITS TN)*. The

telecommunications requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification.

All radio communication and telecommunications equipment shall comply with relevant Australian Communications and Media Authority technical standards and requirements.

# 11.1 STREAMS compatibility

Each vehicle detection system shall communicate with STREAMS either through a field processor or direct Ethernet. If communication with STREAMS is through a field processor, the vehicle detection system shall consist of field processor device driver, enabling communication between the vehicle detection system and the field processor. To satisfy these requirements, the vehicle detection system shall possess STREAMS compatibility certification.

The vehicle detection system shall allow automatic operation and local manual operation independent of STREAMS. Initiation of local operation shall be through separate switch at the site or plug in of PHCS to one serial port. Vehicle detection data shall be communicated to STREAMS while system is in local manual operation.

# 11.2 Communication

The vehicle detection system shall consist of two communication ports

Communication between the vehicle detection system and field processor either shall be direct serial using either EIA/RS 422 or 4-wire EIA/RS 232 through any port, or Ethernet using TCP/IP protocol. Serial protocol shall use recognised industry standards.

The communication requirements specified in MRTS201 *General Equipment Requirements* apply to this Technical Specification. Further communication requirements pertaining to specific kinds of vehicle detectors are listed in the appendices.

# 12 Electromagnetic compatibility

All equipment shall be C-Tick tested and comply with EMI and EMC requirements of AS/NZS 61000.6.1 *Electromagnetic compatibility (EMC) – Generic standards – Immunity for residential, commercial and light-industrial environments* and 61000.6.3 *Electromagnetic compatibility (EMC)*. System-specific requirements are specified in the appendices.

# 13 Installation requirements

The installation requirements listed in MRTS201 *General Equipment Requirements* apply to this Technical Specification.

Only Transport and Main Roads type approved vehicle detector systems shall be used. All vehicle detector systems, except vehicle detectors used for Camera-Detected Offences, must have a current Transport and Main Roads type approval and hold a current STREAMS interface approval.

For motorways which have new asphalt pavements, preformed loops shall be installed. These loops shall be placed below the wearing layer. Where existing concrete pavement sections do not have sufficient asphalt overlays for cutting in loops, type approved non-intrusive technologies would instead be acceptable.

To ensure proper operations of the detector after installation, verification of the detector site by a manufacturer's representative after installation shall be carried out. **Hold Point 3** 

Additional system-specific installation requirements are listed in the appendices.

### 14 Testing and commissioning

The testing and commissioning requirements as defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification.

Tests for checking detector operational performance shall be similar, as applicable, to the tests specified in Appendices A, B and C of AS 2703 for inductive loop detectors.

Specific tests, similar to those shown in AS 2703, are required to demonstrate that the detector system can meet the performance requirements. AS 2703 is the standard for loop detectors, but similar tests for other types of detection system are required.

Additional system-specific testing and commissioning requirements are listed in the appendices.

The operation of the vehicle detector shall be tested in accordance with the manufacturer's Specification. This may include the Principal testing the detector in their traffic management software, which in most cases will be STREAMS. The contractor shall allow the Principal five working days to verify the operation of the detector, after they have notified the Principal of successful testing, as well as provided copies of conforming test results.

# 15 Documentation

The documentation requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification.

Additionally, if required, Form M4300 shall be submitted to the Principal within five working days of installation. The form shall be fully populated to the satisfaction of the Principal. Witness Point 1

Prior to handover, all documentation must be updated to reflect any variations from the original design.

All engineering design drawings shall be certified to meet the requirements of relevant Australian and International Standards by a RPEQ who is practicing within the appropriate / relevant field of engineering.

All updated manufacturer equipment manuals, maintenance manuals, procedures, design documentation, engineering drawings and system specific software and hardware configurations shall be supplied to the Principal for acceptance. Hold Point 4

Additional system-specific documentation requirements are listed in the appendices.

# 16 Training

The training requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification. Additional system specific training requirements are listed in the appendices.

#### 17 Handover

The handing over requirements defined in MRTS201 *General Equipment Requirements* applies to this Technical Specification. Additional system-specific requirements are listed in the appendices.

#### 18 Maintenance

The maintenance requirements defined in MRTS201 *General Equipment Requirements* apply to this Technical Specification. Additional system-specific maintenance requirements are listed in the appendices.

supersonation

# Appendix A - Loop detectors

# A1 General

Vehicle loop detectors use the change of inductance of a wire loop buried below the road pavement surface for the detection of vehicles passing or standing over the loop. The loop can be rectangular, or quadrupole as shown in Standard Drawing 1424.

Although rectangular loops are more popular now than quadrupole loops, they are still in use.

The vehicle loop detector includes a detector loop buried below the road surface, field termination, feeder cable, loop termination panel / block and a detector module that includes a power supply, processing circuity and associated cables.

The vehicle detector loops for traffic operations shall take precedence to vehicle detector loops for enforcement at all time.

Configuration and placement of vehicle detector loops used in enforcement technologies such as redlight camera, and speed camera installations are specific to the particular solution and technology selected for the specific site environment. Hence, the vehicle detector loops configuration and placement details of those installations are excluded from the scope of the Technical Specification.

# A2 Equipment components

Each vehicle loop detector installation shall include

- detector loops
- detector loop field termination
- loop feeder cables
- loop feeder cable terminal panel / block
- cable connecting the loop feeder terminal panel and the detector module
- independent vehicle detector module
- connection between detector module and field processor
- field processor (not for vehicle detectors used for camera-detected offences)
- connection to Principal's telecommunications network in accordance with the provision of MRTS245 *ITS Telecommunications Network (ITS TN)* and necessary hardware
- interface to STREAMS
- telecommunication field cabinet that complies with MRTS226 *Telecommunication Field Cabinets*, and
- provision of power supply that complies with MRTS210 Provision of Mains Power.

# A3 Operational requirements

The performance of the loop detector system shall be based upon vehicles entering the detection zone as specified in AS 2703.

# A3.1 Operating modes

Each detector shall be able to operate in passage or presence mode. The detector shall generally be configured to operate in presence mode. However, where installed as a permanent counting site it shall be configured to operate in passage mode.

Speed measurement in loop detectors shall be implemented using dual loops installed in accordance with the department's *Traffic and Road Use Management Manual, Volume 4 Part 5, Configuration and Placement of Vehicle Detector Sensors* and following standard drawings:

- Standard Drawing 1424 Traffic Signals Detector loops installation details, and / or
- Standard Drawing 1425 Traffic Signals Detector loops placement details
- Standard Drawing 1701 Traffic signals Detector loops counting / right turn loops and diode connection details.

### A3.2 Length of detector feeder cable

The detector module shall, as a minimum, be capable of operating with detector feeder cable lengths specified in AS 2703. Manufacturer of detector shall specify the maximum feeder cable length supported by the detector without compromising performance.

### A3.3 Inductance range and frequency

The detector module shall automatically adjust to operate, when connected to a vehicle detection loop, in accordance with the requirements specified in AS 2703.

Any vehicle detector which does not operate as per manufacturer's Specification shall be highlighted and specifically brought to the Principal's attention. Witness Point 2

Facility shall be available to select the operating frequencies of the detector either on the printed circuit board or via an operator terminal.

# A3.4 Actuation range

The vehicle detector module shall respond to change of inductance between minimum actuation and maximum actuation specified in AS 2703.

# A3.5 Sensitivity settings

Facility shall be available to select sensitivity adjustment of each channel individually with five or more levels suitable to tune for detection of different vehicle types as specified in AS 2703.

#### A3.6 Turn-off time

The turn-off time following an actuation shall comply with the requirements of AS 2703.

#### A3.7 Presence time

The output of presence detector shall comply with the requirements of AS 2703.

#### A3.8 Automatic drift compensation (tracking)

The detector sensor shall automatically compensate for variation of operating conditions as per the requirements of AS 2703.

# A3.9 Recovery from positive inductance change

In the event of sensor unit experiences positive inductance change, the sensor unit shall automatically re-tune.

### A3.10 Susceptibility to interference

The detection system shall comply with the requirements of AS 2703.

### A3.11 Crosstalk

The detector sensor shall employ sequential channel sampling or a similar technique to eliminate crosstalk between channels and shall comply with the requirements of AS 2703.

### A3.12 Leakage to earth

Susceptibility to earth leakage as specified in AS 2703 shall apply to this Technical Specification.

# A4 Mechanical and physical requirements

The detection system components shall be of modular construction to permit minimisation of redundant capacity when installed. Each detector installation shall allow expansion to a minimum of 24 detector loop inputs. The detector equipment shall be supplied in a basic configuration and shall be expandable by installation of additional modules if / when required.

### A4.1 Detector card dimensions

The detector electronics / cards shall comply with the requirements of either ANSI/NEMA TS1 Part 7 or Standard Eurocard Format. Rack-mounted cards shall utilise industry standard connectors.

#### A4.2 Indicators

Each channel of the vehicle loop detector electronics / cards shall have at least one associated LED located on the front faceplate of the detector card. The LEDs shall be illuminated for the duration of each output signal, or if the loop terminals are short-circuited or open-circuited.

Indicators shall comply with the requirements of AS 2703.

# A4.3 Switches and adjustment facilities

Switches and adjustment facilities shall comply with the requirements of AS 2703. The manual re-tune facility shall be externally accessible for each detector channel. Each detector card shall have a reset push-button accessed from the front faceplate.

#### A4.4 Connection facility

The requirements of AS 2703 on the connection facilities for independent sensor units shall apply to this Technical Specification.

# A5 Electrical requirements

The detector system shall comply with the electrical protection requirements of AS 2703.

#### A6 Installation requirements

The loop detector system shall have type approval from the department, or it shall have certification from a NATA accredited test laboratory for the tests listed in Appendix B4 of AS 2703. Test certificates shall be submitted to the Principal prior to commencement of the installation of the detector system.

All vehicle detector systems shall hold a current STREAMS interface certificate, however vehicle detectors used for camera-detected offences do not require STREAMS interface certificate.

The installation of vehicle loop detectors shall be in accordance with MRTS93 *Traffic Signals* in addition to the requirements outlined in this Technical Specification.

The detector feeder cable and detector loop cable shall be in accordance with MRTS257 *Feeder Cable and Loop Cable for Vehicle Detector* 

Installation of detectors shall be in accordance with TRUM Vol 4 Part 5 *Configuration and Placement of Vehicle Detection Sensors,* and the Standard Drawings below:

- SD1424 Traffic Signals Detector loops installation details
- SD1425 Traffic Signals Detector loops placement details
- SD1426 Traffic Signals Detector loops standard configuration
- SD1701 Traffic Signals Detector loops counting/right turn loops and diode connection details, and
- SD1702 Traffic Signals Detector loops motorways and ramp placement, and installation details.

### A6.1 Commencement of Works

At least one full working day prior to intending to install the vehicle detector loops, the Contractor shall notify the Principal of the proposed work. The method of notification is as determined by the Principal.

The Contractor shall not proceed with the works until the Principal has issued acceptance of the proposed works. Hold Point 5

# A6.2 Loop configuration and loop spacing

Loop configuration and loop spacing shall be verified during installation against Transport and Main Roads Standard Drawings for the dimensioned layout that shows the spacing and lane separation. Hold Point 6

#### A6.3 Installation of vehicle detector loops

Vehicle detector loops shall be installed in the locations shown in the department's Standard Drawings with the assistance, where necessary, of Standard Drawings 1424, 1425, 1701 and 1702.

Any sharp edges in the slot which might damage the detector loop cable during installation shall be smoothed off. The slot shall be cleaned out using dry compressed air Witness Point 3

The detector loop cable shall be installed in the slot in a single continuous length and wound with the number of loops stated in the drawings. Both ends of the cable shall terminate in the jointing pit.

The ends of the detector loop cable shall be connected to the detector feed cable in the jointing pit with appropriate ELV rate IP68 enclosure approved by the Principal Witness Point 4

# A6.4 Installation of feeder cables

The feeder cable is intended to be installed in underground ducting with a cable carrying low voltage, and as such is required to comply with the requirements of AS/NZS 3000. Feeder cable shall be installed between a traffic signal controller or standalone vehicle detector and a vehicle detector loop without any intermediate joints.

The unterminated end of the loop feeder cable shall be able to be lifted out of the pit by a minimum of 300 mm and a maximum of 500 mm.

# A6.5 Loop feeder terminal panel

The detector loops shall be connected to the loop feeder terminal panel via loop feeder cables complying with the requirements of MRTS257 *Feeder Cable and Loop Cable for Vehicle Detector*. The loop feeder terminal panel shall provide terminal strips for all detector loops.

Cable looms are to connect the loop feeder terminals to the detector module. The cable looms shall provide a minimum of 24 vehicle detector inputs. Each set of adjacent terminals is denoted a designated pair. The conductors of each pair shall be twisted together at approximately eight turns / metre over the entire length of the loom.

All cables within the harness or loom leading from the loop feeder terminal panel or terminal strip to the detector module shall incorporate screening and / or noise suppression. The loom connecting the loop feeder terminal panel shall have a length of one metre.

The drain conductors for all detector feeder cables shall be connected to earth in the detector cabinet. Loop feeder cables shall be installed so as to minimise likelihood of crosstalk between channels.

# A7 Communication

Where specified, the vehicle detector system shall provide solid state digital outputs to the field processor through a 50-way ribbon cable connector in accordance with MRTS201. The 50-way ribbon cable shall be supplied with the detector system.

# A8 Testing and Commissioning

# A8.1 General

All loops shall be tested during installation, before the saw cut is sealed or the overlay placed on pre-fabricated loops.

All measurements are to be recorded on the appropriate Form M4300, in Appendix D.

The resistance and inductance shall be measured and recorded at different stages of the installation. Resistance, inductance, and insulation resistance of the feeder cable and the loop cable shall be measured and recorded separately as well as combined after joining.

The testing of the loops is same for both quadrupole and rectangular loop. The major determining factors on the inductance value of a loop are the configurations and the dimensions of the loop.

All Works shall meet the requirements of the AS/NZS3000 *Wiring Rules*, MRTS228 *Electrical Switchboards* and the local electricity supply authority.

# A8.2 Testing equipment requirements

Inductance, resistance and impedance measurements of vehicle detection loops shall be measured using a test instrument with the following performance characteristics:

- measurement tolerance of ± 3%
- measurement range of 40 to 800 µH
- inductance measurement at loop tuned frequency
- self-tuning in the range of 40 to 800 μH
- input loop reading resonation between 15 kHz and 140 kHz
- a Q of ≥ 3 at typical resonant frequency for loops of the specified inductance range
- loop insulation integrity verification > 100 M $\Omega$  and within ± 10% accuracy, and
- DC resistance range  $0.3 \Omega$  to  $9 \Omega$ .

The Contractor shall nominate the device to be used and provide a copy of its current calibration certificate to the Principal before testing commences. Witness Point 3

# A8.3 Testing of feeder cable

The feeder cable shall be tested after installation and before being connected to the loop and the detector.

The drain conductors for all detector feeder cables are to be connected to earth in the detector sensor cabinet.

Earth continuity measurements for the drain conductor shall not exceed drain cable resistance as specified in MRTS257 *Feeder Cable and Loop Cable for Vehicle Detector*.

Insulation resistance between the two cores and between earth and either core shall exceed 1 M $\Omega$ .

Cables that fail any of these tests shall be removed and new cables installed.

# A8.4 Testing of individual loop

For loops fabricated on-site, all loop measurements shall be taken and recorded when the loop cable has been laid in the saw cut. The retaining wedges shall be in place to ensure the loop cable does not move in the saw cut. The lead-in cable, where possible, from the loop, shall be placed in its saw cut. Any lead-in cable not placed in a saw cut shall be twisted to have a minimum of one full turn every 10 cm (10 turns per meter) before any measurements are taken.

For loops that are prefabricated, all measurements shall be taken and recorded when the loop cable has been laid in place and secured to ensure the loop cable does not move. The lead in cable from the loop shall be twisted to have a minimum of one full turn every 10 cm before any measurements are taken.

The loop internal resistance and inductance shall then be measured.

Record the measurements for all loops on Form M4300. Any measurements which are not within the operational requirements shall be highlighted and specifically brought to the Principal's attention before the close of business on the next working day. Witness Point 4

# A8.5 Testing of loop cable and feeder cable circuit

The inductance and resistance shall be measured again after the loop is connected to the loop feeder cable and before the connection joint is sealed. The results of these measurements should be the sum of the previous measurement for the loop and the increased resistance and inductance of the loop feeder cable.

Any measurements which are not within 15% of the values calculated using parameters specified in MRTS257 *Feeder Cable and Loop Cable for Vehicle Detector* shall be highlighted and specifically brought to the Principal's attention before the close of business on the next working day. The final measurements for all loop circuits shall be recoded on Form M4300 and submitted to the Principal within five working days of installation. **Witness Point 5** 

For loops connected in series the formulae for calculations are:

 $\begin{aligned} R_t &= R_1 + R_2 & \text{Resistance in Ohms } (\Omega) \\ L_t &= L_1 + L_2 & \text{Inductance in micro Henry } (\mu H) \\ \text{For loops connected in parallel the formulae are:} \\ R_t &= (R_1 \times R_2) / (R_1 + R_2) \text{ Resistance in Ohms } (\Omega) \end{aligned}$ 

 $L_t = (L_1 \times L_2) / (L_1 + L_2)$  Inductance in micro Henry (µH)

# A8.6 Testing during installation

Insulation resistance, inductance and resistance of the loops shall be measured prior to installation and before the saw cut is sealed or the overlay placed on prefabricated loops.

The feeder cable shall be tested after installation and before being connected to the loop and the detector.

Each circuit shall be tested again when the loop feeder is connected to the loop lead-in cable before the connection is sealed. These measurements shall be recorded for each loop. The original record shall be provided to the Principal and a copy shall be placed in the cabinet housing the vehicle detector.

Resistance and inductance of the conductors shall comply with the cable characteristics in MRTS257 *Feeder Cable and Loop Cable for Vehicle Detector.* 

Insulation resistance between the two cores and between earth and either core shall exceed 1 MΩ.

Cables that fail any of these tests shall be removed and new cables installed.

Where two or more loops are connected to the one vehicle detector sensor channel, the inductance and the resistance of the loop and feeder cable circuit is to be measured as a total.

Any measurements which are not complying to this Technical Specification shall be highlighted and specifically brought to the Principal's attention before the close of business on the next working day.

After connection of the loop circuit to the vehicle detector, the operation of the vehicle detector shall be tested in accordance with the manufacturer's specification, including testing of the system using the Principal's Traffic Management System.

# **Appendix B - Infrared Vehicle Detectors**

This is a new appendix on the requirements of infrared vehicle detectors.

#### B1 General

Infrared Vehicle Detectors (IRVD) use the events of break-and-make of infrared beams between transmitter and receiver mounted across the road, in perpendicular to traffic flow, for the detection of vehicle passing, and the calculation of vehicle parameters. Break-and-make events of the infrared beams occur when the infrared beams are blocked by the wheels of the vehicles. In most applications, multiple beams are used for obtaining vehicle parameters.

The requirements listed in this Appendix are additional requirements specific to this particular type of technology and are to be read in conjunction with the requirements listed in the main sections of the document.

#### B2 Equipment components

Each IRVD installation shall include:

- infrared transmitter
- infrared receiver
- provision of power supply that complies with MRTS210 General Equipment Requirements
- TCP/IP connection between infrared receiver and field processor / network switch using CAT 5 cable or alternative 3G wireless connection
- field processor, and
- connection to the Principal's telecommunications network in accordance with the provision of MRTS245 ITS Telecommunications Network (ITS TN) and necessary hardware.

#### B3 Functional requirements

In addition to the functional requirements listed in Clause 5, the following specific requirements are applicable to IRVD systems:

- remote monitoring of infrared transmitter power, receiver power, beam degradation alarm or lens block alarm
- remote monitoring of battery parameters, such as voltage level and remaining battery capacity if batteries are used as power source
- method of verifying alignment (height, roll, pitch and yaw) for installation in existing roads without road closure and additional tools to assist installation in new constructions, and
- remote monitoring of alignment details, including tilt, pitch, yaw and height of the beam with respect to ground or correction of the alignment through the Principal's telecommunication network.

#### **B4** Operational requirements

The following additional operational requirements are applicable to IRVD.

# B5 Power

The infrared beam shall have sufficient power to avoid system performance degradation due to soiling or other environmental effects which lead to frequent maintenance. The maintenance interval shall be more than one year. The power level of the IR beam shall not cause any safety or health hazards.

# **B5.1** Modulation

The beams shall be suitably modulated to avoid environmental effects.

### B5.2 Misalignment

The transmitter and receiver shall be able to operate with minimum of 10-degree misalignment.

# B5.3 Transmitter power and receiver sensitivity adjustment

The transmitter power and receiver sensitivity shall be able to adjust in order to meet requirements at the site. The adjustment of power and receiver sensitivity shall be either automatic or manual.

# B6 Mechanical and physical requirements

Infrared transmitter and receiver mounting arrangement shall consist of independent adjustment in all three axes for alignment together with locking arrangement to avoid change of alignment due to vibration and other environmental effects.

Printed circuit boards in the system shall be coated with protective layer to protect against moisture and water ingress. Transmitter and receiver shall be rated for IP 68 in accordance with AS 60529 *Degrees of protection provided by enclosures (IP Code)*.

# **B7** Electrical requirements

Only departmental type approved infrared vehicle detector systems shall be used. All vehicle detector systems must have a current departmental type approval and hold a current STREAMS interface approval.

Vehicle detectors used for camera-detected offences, do not require STREAMS interface approval.

Power supply to the transmitter and receiver shall be ELV. Whenever mains power is used as power source, power converter equipment shall be installed in a separate cabinet.

# B8 Electromagnetic compatibility / safety approval

IRVD shall have RCM compliance and safety approval shall be compliant to AS/NZS 60950.1.

# **B9** Installation requirements

Only departmental type approved vehicle detector systems shall be used. All vehicle detector systems must have a current departmental type approval and hold a current STREAMS interface approval.

Installation of IRVD system shall meet the following requirements:

- transmitter and receiver shall be perpendicular to the traffic direction
- transmitter and receiver shall be aligned (height, roll, pitch and yaw)
- external housing shall be flushed with curb to avoid build-up of litter
- concrete apron to road edge shall be installed if required
- IR beam shall clear crown of the road at least by 50 mm, and

• vehicle bodies shall not obstruct the IR beam in near lanes.

The IRVD shall be configured to the road geometry.

#### B10 Testing and commissioning

IRVD installations shall confirm the following aspects of alignment using software or hard tool:

- height
- roll
- pitch, and
- yaw.

Details of beam power level at the receiver shall be tested using software or other tool and shall meet the requirements of the manufacturer.

The testing of the IRVD system shall be in accordance with the manufacturer's recommendations.

### Hold Point 7

Before the handover of the system the contractor shall notify the Principal in writing of the successful testing and provide copies of conforming test results and then allow the Principal five working days to verify the operation of the IRVD system. Witness Point 6

# **Appendix C - Radar Vehicle Detectors**

This is a new appendix on the requirements of radar vehicle detectors.

#### C1 General

Radar vehicle detectors (RVD) use reflection of transmitted electromagnetic radar signal, from the vehicles, for the detection of vehicle passing and calculation of vehicle parameters. The radar signal transmitter is mounted on the roadside perpendicular to the traffic flow. In most applications, multiple radar signal beams are used for obtaining vehicle parameters.

The requirements listed in this appendix are additional requirements specific to this particular type of technology and are to be read in conjunction with the requirements listed in the main sections of the document.

#### C2 Equipment components

Each radar vehicle detector installation shall include:

- 1. radar transmitter and receiver
- 2. provision of power supply complying with MRTS210 Provision of Mains Power
- 3. RS 232, RS 285 or TCP / IP connection between radar unit and field processor / network switch using standard cables or CAT 5 cable as applicable, and
- 4. connection to the Principal's telecommunications network in accordance with the provision of MRTS245 *ITS Telecommunications Network (ITS TN)* and necessary hardware.

#### C3 Functional requirements

In addition to the functional requirements listed in Clause 5, the following specific requirements are applicable to RVD systems:

- 1. RVD system configuration shall be automatic or manual
- 2. automatic configuration shall include defining of lanes within the detection area using probability density function of the detected vehicles
- 3. manual configuration minimum increment level shall be less than 0.25 m
- 4. remote monitoring of transmitted power and average receiver signal strength, and
- 5. remote monitoring of input voltage.

#### C4 Operational requirements

The following additional operational requirements are applicable to RVD.

#### C4.1 Frequency

Radar signal frequency shall be ISM unlicensed band or other frequency band with appropriate license.

#### C4.2 Side lobes

Side lobes power level shall be less than - 40 dB to avoid interference with other equipment.

# C4.3 Bandwidth

Bandwidth of the radar signal shall be greater than 240 MHz in order to achieve un-windowed radar resolution of at least 0.75 m.

### C4.4 Transmitter power and receiver sensitivity adjustment

Transmitter power and receiver sensitivity shall be able to adjust in order to meet requirements of various locations. The adjustment of power and receiver sensitivity shall be either automatic or manual.

# C4.5 Beamwidth stability

Beamwidth stability of the transmitted radar signal shall be more than 1%.

### C4.6 Frequency channels

Number of frequency channels should facilitate installation of multiple units in the vicinity without interference and minimum of four channels is preferable.

### C5 Mechanical and physical requirements

The radar unit shall be mounted directly to the mounting assembly fastened to a pole or other structure and have facility of movement in all three axis for alignment.

The printed circuit boards in the system shall be coated with protective layer to protect against moisture and water. Radar unit shall be rated for IP 68 in accordance with AS 60529. Radar unit housing shall be resistive to UV, fungus and corrosion.

#### C6 Performance requirements

The following additional performance requirements are applicable to RVD:

- 1. minimum detection range less than 2 m
- 2. maximum detection range greater than 80 m
- 3. number of detection lanes greater than 10
- 4. any variation of lane width
- 5. detection over barrier whenever more than 50% of the vehicle is visible to the radar, and
- 6. minimum separation between vehicles shall be less than 1.7 m.

#### C7 Electrical requirements

Only departmental type approved vehicle detector systems shall be used. All vehicle detector systems must have a current departmental type approval and hold a current STREAMS interface approval.

Vehicle detectors used for camera-detected offences, do not require STREAMS interface approval.

If power supply to the radar unit is ELV, the power converter equipment shall be installed in a separate cabinet.

# C8 Installation requirements

Site-specific installation plan shall be approved by the system manufacturer or system designer approved by the manufacturer. The site-specific installation plan shall contain installation details of the radar vehicle detector.

# C9 Testing of Radar Vehicle Detector

The testing of the RVD system shall be in accordance with the manufacturer's recommendations. **Hold Point 8** 

Before the handover of the system the contractor shall notify the Principal in writing of the successful testing and provide copies of conforming test results and then allow the Principal five working days to verify the operation of the RVD system. Witness Point 7



# Appendix D - Form M4300

# Vehicle Detector Loop Settings and Measurements Record

| Location       |                                  |                   | I                  | Detector man      | ufacturer's n      | ame                            |                     | Date of loo        | p installatio               | 'n                |                                     |
|----------------|----------------------------------|-------------------|--------------------|-------------------|--------------------|--------------------------------|---------------------|--------------------|-----------------------------|-------------------|-------------------------------------|
|                |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| Site ider      | ntification nu                   | mber              |                    | Detector mod      | lel                |                                |                     | Date data c        | ollected                    |                   |                                     |
|                |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
|                |                                  | Loop              |                    | Loop and f        | eeder cable        |                                | 0                   | Detect             | tor data                    |                   |                                     |
| Loop<br>number | Insulation<br>resistance<br>(MΩ) | Resistance<br>(Ω) | Inductance<br>(µH) | Resistance<br>(Ω) | Inductance<br>(µH) | Sensor &<br>channel<br>numbers | Sensitivity setting | Frequency<br>(kHz) | Mode<br>PAsage/<br>Presence | Resistance<br>(Ω) | Q or<br>Manufacturer<br>information |
| 1.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 2.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 3.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 4.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 5.             |                                  |                   |                    |                   |                    | -                              |                     |                    |                             |                   |                                     |
| 6.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 7.             |                                  |                   |                    |                   | V                  |                                |                     |                    |                             |                   |                                     |
| 8.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 9.             |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 10.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 11.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 12.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 13.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 14.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 15.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |
| 16.            |                                  |                   |                    |                   |                    |                                |                     |                    |                             |                   |                                     |