

Main Roads Specification

MRS14

Road Furniture

SUPERSEDED

June 09

IMPORTANT INFORMATION

The requirements of this document represent Technical Policy of the department and contain Technical Standards. Compliance with the department's Technical Standards is mandatory for all applications for the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

This document will be reviewed from time to time as the need arises and in response to improvement suggestions by users. Please send your comments and suggestions to the feedback email given below.

FEEDBACK

Your feedback is welcomed. Please send to mr.techdocs@tmr.qld.gov.au.

COPYRIGHT

© State of Queensland (Department of Transport and Main Roads) 2009

Copyright protects this publication. Except for the purposes permitted by and subject to the conditions prescribed under the Copyright Act, reproduction by any means (including electronic, mechanical, photocopying, microcopying or otherwise) is prohibited without the prior written permission of the department. Enquiries regarding such permission should be directed to the Road & Delivery Performance Division, Queensland Department of Transport and Main Roads.

DISCLAIMER

This publication has been created for use in the design, construction, maintenance and operation of road transport infrastructure in Queensland by or on behalf of the State of Queensland.

Where the publication is used in other than the department's infrastructure projects, the State of Queensland and the department gives no warranties as to the completeness, accuracy or adequacy of the publication or any parts of it and accepts no responsibility or liability upon any basis whatever for anything contained in or omitted from the publication or for the consequences of the use or misuse of the publication or any parts of it.

If the publication or any part of it forms part of a written contract between the State of Queensland and a contractor, this disclaimer applies subject to the express terms of that contract.

June 09

Table of Contents

	Page
1 INTRODUCTION.....	1
2 MEASUREMENT OF WORK.....	1
2.1 Standard Work Items	1
2.2 Work Operations	1

SUPERSEDED

SUPERSEDED

Road Furniture

1 INTRODUCTION

This Specification applies to the demolition and re-erection of and the supply and construction of road edge guide posts, fencing and gates.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Main Roads Specifications and Technical Standards Manual.

2 MEASUREMENT OF WORK

2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the standard work items covered by this specification are listed in Table 2.1.

Table 2.1 – Standard Work Items

Standard Item No.	Description	Unit of Measurement
	Removal, Demolition and Re-erection	
6101	Demolition of road furniture, as listed in Clause 3 of Annexure MRTS14.1	lump sum
6103	Removal and salvage of road furniture, as listed in Clause 1.1 of Annexure MRTS14.1	lump sum
6104	Removal and re-erection of road furniture, as listed in Clause 4 of Annexure MRTS14.1	lump sum
	Guidance and Information Systems	
6111	Road edge guide posts	each
	Roadside Structures	
6181	Fencing, [height] mm high, [type]	m
6182	Gates, [height] mm high, [width] mm wide, [type]	each

2.2 Work Operations

Item 6101 Demolition of road furniture, as listed in Clause 3 of Annexure MRTS14.1

Work Operations incorporated in the above items include –

- Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- Carrying out excavation where necessary;
- Demolishing existing road furniture as listed;
- Utilising or disposing of excavated and demolished material; and
- Backfilling and finishing resulting excavations.

Item 6103 Removal and salvage of road furniture, as listed in Clause 1.1 of Annexure MRTS14.1

Work Operations incorporated in the above item include –

- Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- Carrying out excavation where necessary;
- Careful dismantling and removal of existing road furniture as listed;
- Demolition of any agreed non-salvageable part of the existing installation;

- e) Utilising or disposing of excavated and demolished material;
- f) Transporting salvaged material to storage site;
- g) Safe storage of salvaged material at storage site; and
- h) Backfilling and finishing resulting excavations.

Item 6104 Removal and re-erection of road furniture, as listed in Clause 4 of Annexure MRTS14.1

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Carrying out excavation where necessary;
- c) Careful dismantling and removal of existing road furniture as listed;
- d) Demolition of any agreed non-salvageable part of the existing installation;
- e) Utilising or disposing of excavated and demolished material;
- f) Backfilling and finishing resulting excavations;
- g) Safe storage of salvaged material until required for re-erection;
- h) Supply of new materials necessary for re-erection; and
- i) Re-erection of salvaged material.

Item 6111 Road edge guide posts

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supplying all materials;
- c) Fabrication of guide posts;
- d) Application of all coatings;
- e) Affixing delineators; and
- f) Installation of posts.

Item 6181 Fencing, [height] mm high, [type]

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Localised clearing;
- c) Supply of all materials;
- d) Installation of posts, pickets and stays;
- e) Running, fixing and straining fencing wire; and
- f) Installation of chainwire, wire netting and/or welded mesh.

Item 6182 Gates, [height] mm high, [width] mm wide, [type]

Work Operations incorporated in the above item include –

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*;
- b) Supply of all materials;
- c) Fabrication of gates; and
- d) Installation of the gates.