

Superseded

**Specification (Measurement)**

**Transport and Main Roads Specifications  
MRS14 Road Furniture**

**July 2017**

Superseded

## Copyright



<http://creativecommons.org/licenses/by/3.0/au/>

© State of Queensland (Department of Transport and Main Roads) 2017

**Feedback:** Please send your feedback regarding this document to: [tmr.techdocs@tmr.qld.gov.au](mailto:tmr.techdocs@tmr.qld.gov.au)

## Contents

<b>1</b>	<b>Introduction .....</b>	<b>1</b>
<b>2</b>	<b>Measurement of work .....</b>	<b>1</b>
2.1	Standard Work Items .....	1
2.2	Work Operations .....	2
2.3	Method of measurement .....	9
2.3.1	<i>Supply of regulatory, warning and hazard signs .....</i>	<i>9</i>
2.3.2	<i>Installation of regulatory, warning and hazard Signs .....</i>	<i>9</i>
2.3.3	<i>Supply of direction and information signs .....</i>	<i>9</i>
2.3.4	<i>Installation of direction and information signs .....</i>	<i>10</i>
2.3.5	<i>Grids .....</i>	<i>10</i>
2.4	Project signs .....	10
2.4.1	<i>Items supplied by the Principal .....</i>	<i>10</i>
2.4.2	<i>Incidental materials .....</i>	<i>10</i>
2.4.3	<i>Payment .....</i>	<i>10</i>

## 1 Introduction

This Specification applies to the demolition and re-erection of and the supply and construction of road edge guide posts, fencing, gates road signs, grids, steel beam guardrail, tensioned wire rope barrier systems, steel traffic barriers and concrete traffic barriers.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications* and other Specifications as appropriate.

This Specification forms part of the Transport and Main Roads Specifications Manual.

## 2 Measurement of work

### 2.1 Standard Work Items

In accordance with the provisions of Clause 2.1.3 of MRS01 *Introduction to Specifications*, the Standard Work Items covered by this Specification are listed in Table 2.1.

**Table 2.1 – Standard Work Items**

Standard Item No.	Description	Unit of Measurement
50001	Demolition of road furniture, as listed in Clause 3 of Annexure MRTS14.1	lump sum
50002	Removal and salvage of road furniture, as listed in Clause 1.1 of Annexure MRTS14.1	lump sum
50003	Removal and re-erection of road furniture, as listed in Clause 4 of Annexure MRTS14.1	lump sum
<b>Guidance and information systems</b>		
50051	Road edge guide posts	each
50052	Supply of regulatory, warning and hazard sign faces, as listed in Clause 1.3 of Annexure MRS14.1	lump sum
50053	Supply of regulatory, warning and hazard sign faces, [sign type]	each
50054	Supply of direction and information sign faces, as listed in Clause 2.3 of Annexure MRS14.1	lump sum
50055	Supply of direction and information sign faces, as listed in Clause 2.3 of Annexure MRS14.1	m <sup>2</sup>
50056	Installation of regulatory, warning and hazard signs, as listed in Clause 1.3 of Annexure MRS14.1	lump sum
50057	Installation of regulatory, warning and hazard signs, [number of posts]	each
50058	Installation of direction and information signs, as listed in Clause 2.3 of Annexure MRS14.1	lump sum
50059	Installation of direction and information signs, [sign number]	each
50060	Installation of direction and information signs, [sign size]	each
50061	Supply, erection and removal of project signs	lump sum
<b>Roadside structures</b>		
50151	Grid [type]	each
50152	Grid with vermin and dog fencing [type]	each

Standard Item No.	Description	Unit of Measurement
50153	Concrete traffic barrier, [type], [with   without conduit], [with   without dowels]	m
50154	Concrete traffic barrier at wall or pier, [type], [with   without conduit], [with   without dowels]	m
50155	Concrete traffic barrier median terminal, [type], [with   without conduit], [with   without dowels]	each
50156	Galvanised cover assembly at opening for light pole	each
50157	Galvanised cover assembly at opening for cable pit, number [pit number   type]	each
50158	Split carriageway concrete traffic barrier, [type], [with   without conduit], [with   without dowels]	m
50159	Precast concrete barrier	m
50160	Steel beam guardrail, w beam	m
50161	Steel beam guardrail, thrie beam	m
50162	Steel beam guardrail, terminal type [number]	each
50163	Steel beam guardrail, transition type [number]	each
50164	Installation of tensioned wire rope barrier system including all necessary intermediate anchors	m
50165	Tensioned wire rope barrier system terminal anchors	each
50166	Barrier end treatment	each
50167	Fencing, [height] mm high, [type]	m
50168	Gates, [height] mm high, [width] mm wide, [type]	each
50169	Steel traffic barriers	m

## 2.2 Work Operations

### Item 50001 Demolition of road furniture, as listed in Clause 3 of Annexure MRTS14.1

Work Operations incorporated in the above items include:

- Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- carrying out excavation where necessary
- demolishing existing road furniture as listed
- utilising or disposing of excavated and demolished material
- backfilling and finishing resulting excavations.

### Item 50002 Removal and salvage of road furniture, as listed in Clause 1.1 of Annexure MRTS14.1

Work Operations incorporated in the above item include:

- Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- carrying out excavation where necessary

- c) careful dismantling and removal of existing road furniture as listed
- d) demolition of any agreed non-salvageable part of the existing installation
- e) utilising or disposing of excavated and demolished material
- f) transporting salvaged material to storage site
- g) safe storage of salvaged material at storage site
- h) backfilling and finishing resulting excavations.

**Item 50003      Removal and re-erection of road furniture, as listed in Clause 4 of Annexure MRTS14.1**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) carrying out excavation where necessary
- c) careful dismantling and removal of existing road furniture as listed
- d) demolition of any agreed non-salvageable part of the existing installation
- e) utilising or disposing of excavated and demolished material
- f) backfilling and finishing resulting excavations
- g) safe storage of salvaged material until required for re-erection
- h) supply of new materials necessary for re-erection
- i) re-erection of salvaged material.

**Item 50051      Road edge guide posts**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supplying all materials
- c) fabrication of guide posts
- d) application of all coatings
- e) affixing delineators
- f) installation of posts.

**Item 50052      Supply of regulatory, warning and hazard sign faces, as listed in Clause 1.3 of Annexure MRS14.1**

**Item 50053      Supply of regulatory, warning and hazard sign faces, [*sign type*]**

**Item 50054      Supply of direction and information sign faces, as listed in Clause 2.3 of Annexure MRS14.1**

**Item 50055      Supply of direction and information sign faces, as listed in Clause 2.3 of Annexure MRS14.1**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of the sign panels
- d) attachment of stiffeners, where applicable
- e) application of protective coatings, colour coatings, reflective coatings and messages
- f) reference marking of signs
- g) delivery to the site.

**Item 50056      Installation of regulatory, warning and hazard signs, as listed in Clause 1.3 of Annexure MRS14.1**

**Item 50057      Installation of regulatory, warning and hazard signs, [*number of posts*]**

**Item 50058      Installation of direction and information signs, as listed in Clause 2.3 of Annexure MRS14.1**

**Item 50059      Installation of direction and information signs, [*sign number*]**

**Item 50060      Installation of direction and information signs, [*sign size*]**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of posts
- c) supply of brackets, saddles and fixings
- d) supply and fabrication of sign frames, where applicable
- e) installation of the posts
- f) installation of frames, where applicable
- g) installation of the sign faces to posts or frames.

**Item 50061      Supply, erection and removal of project signs**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials except those materials supplied by the Principal
- c) transport of signs and supports
- d) installation of posts
- e) installation of the sign faces to posts or frames
- f) maintenance of project signs
- g) removal of project signs and cleaning up.

**Item 50151      Grid [type]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) carrying out excavations
- c) utilisation or disposal of the excavated material
- d) supply of all materials
- e) fabrication and galvanising of grid frames
- f) construction of concrete abutments
- g) backfilling behind abutments
- h) construction of concrete slab
- i) installation of grid frames
- j) construction of grouted stone pitching at abutment wings
- k) installation of four guide posts and width marker, where necessary
- l) installation of two 2400 mm wide, 1650 mm high fence strainer panels and fencing between strainer panel and guide posts
- m) reinstatement of any pavement, pavement surfacing, fencing and road furniture.

**Item 50152      Grid with vermin and dog fencing [type]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) carrying out excavations
- c) utilisation or disposal of the excavated material
- d) supply of all materials
- e) fabrication and galvanising of grid frames
- f) construction of concrete abutments and wing walls
- g) backfilling behind abutments and wing walls
- h) construction of concrete slab
- i) installation of grid frames
- j) installation of four guide posts and width marker, where necessary
- k) installation of 66 metres of 1950 mm high vermin and dog fencing including 10 strainer panels
- l) installation of two 2500 mm wide, 1950 mm high gates
- m) reinstatement of any pavement, pavement surfacing, fencing and road furniture.

**Item 50153      Concrete traffic barrier, [type], [with | without conduit], [with | without dowels]**

**Item 50154      Concrete traffic barrier at wall or pier, [type], [with | without conduit], [with | without dowels]**

**Item 50155 Concrete traffic barrier median terminal, [type], [with | without conduit], [with | without dowels]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) preparation of surface
- c) supply of all materials
- d) installation of electrical conduit and cable pits, where applicable
- e) installation of dowels, where applicable
- f) installation of steel reinforcing
- g) erection of formwork
- h) installation of guardrail anchor bolts
- i) placement of concrete
- j) installation of expansion joint
- k) installation of delineators.

**Item 50156 Galvanised cover assembly at opening for light pole**

**Item 50157 Galvanised cover assembly at opening for cable pit, number [pit number | type]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of cover assembly
- d) installation of fixing angles
- e) installation of cement mortar infill over conduit
- f) installation of cover plates.

**Item 50158 Split carriageway concrete traffic barrier, [type], [with | without conduit], [with | without dowels]**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) preparation of surface
- c) supply of all materials
- d) installation of electrical conduit and cable pits, where applicable
- e) installation of dowels, where applicable
- f) installation of steel reinforcing
- g) extruding or forming and casting of fibre reinforced concrete traffic barrier
- h) installation of compressible filler, where required

- i) installation of expansion joints and contraction joints
- j) installation of delineators

**Item 50159      Precast concrete barrier**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) preparation of surface
- c) supply of all materials
- d) supply and transport of precast concrete barrier
- e) installation of barrier including permanent connectors as specified
- f) fill stanchion holes.

**Item 50160      Steel beam guardrail, w beam**

**Item 50161      Steel beam guardrail, thrie beam**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of components
- d) galvanising of components
- e) installation of posts
- f) erection of guard-rail.

**Item 50162      Steel beam guardrail, terminal type [number]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of components
- d) galvanising of components
- e) installation of posts
- f) installation of anchor cable assembly
- g) erection of guardrail
- h) supply and installation of TC 1151 signs.

**Item 50163      Steel beam guardrail, transition type [number]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials

- c) fabrication of components
- d) galvanising of components
- e) installation of connector brackets
- f) installation of posts
- g) erection of guardrail.

**Item 50164      Installation of tensioned wire rope barrier system including all necessary intermediate anchors**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supplying all materials
- c) fabrication of all components
- d) application of all protective coatings
- e) installation of barrier system
- f) installation of delineators.

**Item 50165      Tensioned wire rope barrier system terminal anchors**

Work operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of components
- d) application of all protective coatings
- e) installation of terminal anchor complete.

**Item 50166      Barrier end treatment**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) preparation of site
- c) supply of all materials
- d) installation of proprietary barrier end treatment.

**Item 50167      Fencing, [height] mm high, [type]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) localised clearing
- c) supply of all materials
- d) installation of posts, pickets and stays

- e) running, fixing and straining fencing wire
- f) installation of chainwire, wire netting and/or welded mesh.

**Item 50168 Gates, [*height*] mm high, [*width*] mm wide, [*type*]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) supply of all materials
- c) fabrication of gates
- d) installation of the gates.

**Item 50169 Steel traffic barriers**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) preparation of Site
- c) supply of all Materials
- d) installation of steel traffic barrier system.

**2.3 Method of measurement**

**2.3.1 Supply of regulatory, warning and hazard signs**

The supply of regulatory, warning and hazard signs shall be measured by either Method A or Method B as stated as Clause 1.1 of Annexure MRS14.1.

Where Method A applies, the supply of all regulatory, warning and hazard signs shall be included in a single Work Item measured as a lump sum. The signs included in the lump sum Work Item shall be as listed in Clause 1.3 of Annexure MRS14.1.

Where Method B applies, the supply of regulatory, warning and hazard signs shall be assigned individual Work Items on the basis of sign type and measured as each sign.

**2.3.2 Installation of regulatory, warning and hazard Signs**

The installation of regulatory, warning and hazard signs shall be measured by either Method A or Method B as stated in Clause 1.2 of Annexure MRS14.1.

Where Method A applies, the installation of all regulatory, warning and hazard signs shall be included in a single Work Item measured as a lump sum. The signs included in the lump sum Work Item shall be as listed in Clause 1.3 of Annexure MRS14.1.

Where Method B applies, the installation of regulatory, warning and hazard signs be assigned several Work Items on the basis of the number of support posts, and measured as each sign.

**2.3.3 Supply of direction and information signs**

The supply of direction and information signs shall be measured by either Method A or Method B as stated in Clause 2.1 of Annexure MRS14.1.

Where Method A applies, the supply of all direction and information sign faces shall be included in a single Work Item measured as a lump sum. The signs included in the lump sum Work Item shall be as listed in Clause 2.3 of Annexure MRS14.1.

Where Method B applies, the supply of direction and information sign faces shall be included in a single Work Item and measured as square metres of sign face. The signs included in the lump sum work Item shall be as listed in Clause 2.2 of Annexure MRS14.1.

#### **2.3.4 Installation of direction and information signs**

The installation of direction and information signs shall be measured by either Method A, Method B or Method C as stated in Clause 2.2 of Annexure MRS14.1.

Where Method A applies, the installation of all direction and information signs shall be included in a single Work Item measured as a lump sum. The signs included in the lump sum Work Item shall be as listed in Clause 2.3 of Annexure MRS14.1.

Where Method B applies, the installation of direction and information signs shall be assigned individual Work Items on the basis of the sign number, and measured as each sign.

Where Method C applies, the installation of direction and information signs shall be assigned several Work Items on the basis of sign size, and measured as each sign.

#### **2.3.5 Grids**

Specific Item Numbers for grids used in the Schedule of Rates shall be deemed to represent the work associated with the particular reference locations stated in Clause 3 of Annexure MRS14.1.

### **2.4 Project signs**

#### **2.4.1 Items supplied by the Principal**

Any project signs and support posts which are to be supplied by the Principal are shown on the Principal Supplied Material List (Form C6827). Such items will be supplied free on truck at the location listed on the Principal Supplied Material List.

#### **2.4.2 Incidental materials**

All materials not specifically included on the Principal Supplied Material List, but necessary for the assembly, erection and maintenance of Principal-supplied items, including saddles, fixings or other erection hardware, shall be supplied by the Contractor.

#### **2.4.3 Payment**

Sixty percent of any lump sum item included in the Schedule of Rates for project signs shall be paid following the erection of the signs. The balance of such lump sum item shall be paid following dismantling, reinstating footing holes and returning posts, and signs to the nominated location.

Superseded