

Superseded

**Specification (Measurement)**

**Transport and Main Roads Specifications  
MRS256 Power Cables**

**July 2023**



## Copyright

© The State of Queensland (Department of Transport and Main Roads) 2023.

## Licence



This work is licensed by the State of Queensland (Department of Transport and Main Roads) under a Creative Commons Attribution (CC BY) 4.0 International licence.

## CC BY licence summary statement

In essence, you are free to copy, communicate and adapt this work, as long as you attribute the work to the State of Queensland (Department of Transport and Main Roads). To view a copy of this licence, visit: <https://creativecommons.org/licenses/by/4.0/>

## Translating and interpreting assistance



The Queensland Government is committed to providing accessible services to Queenslanders from all cultural and linguistic backgrounds. If you have difficulty understanding this publication and need a translator, please call the Translating and Interpreting Service (TIS National) on 13 14 50 and ask them to telephone the Queensland Department of Transport and Main Roads on 13 74 68.

## Disclaimer

While every care has been taken in preparing this publication, the State of Queensland accepts no responsibility for decisions or actions taken as a result of any data, information, statement or advice, expressed or implied, contained within. To the best of our knowledge, the content was correct at the time of publishing.

## Feedback

Please send your feedback regarding this document to: [tmr.techdocs@tmr.qld.gov.au](mailto:tmr.techdocs@tmr.qld.gov.au)

**Contents**

- 1 Introduction .....1**
- 2 Measurement of Works .....1**
  - 2.1 Standard Work Items .....1
  - 2.2 Work Operations.....2
  - 2.3 Calculation of quantities .....3

Superseded

## 1 Introduction

This Specification applies to the supply and installation of power cables for the supply of electrical power to electrical installations, including traffic signal installations and Rates-2 and Rate-3 road lighting installations.

This Specification shall be read in conjunction with MRS01 *Introduction to Specifications*, MRTS256 *Power Cables* and other Specifications as appropriate.

This Specification forms part of the Transport and Main Roads Specifications Manual.

## 2 Measurement of Works

### 2.1 Standard Work Items

In accordance with the provisions of Clause 2 of MRS01 *Introduction to Specifications*, the Standard Work Items covered by this Specification are listed in Table 2.1.

Work Items 67104 and 67112 have been modified to cover all cables (i.e. including ITS power cables)

**Table 2.1 – Standard Work Items**

Standard Item No.	Description	Unit of Measurement
67101	Supply of underground road lighting cable, [conductor size], [number of cores] cores, [core insulation], [sheath insulation], [conductor material]	m
67102	Supply of aerial road lighting cable, [conductor size], [number of cores] cores, [core insulation], [sheath insulation], [conductor material]	m
67103	Supply of traffic signal cable, [conductor size], [number of cores] cores, [core insulation], [sheath insulation], [conductor material]	m
67104	Supply of cable, [usage], [conductor size], [number of cores] cores, [core insulation], [sheath insulation], [conductor material]	m
67105	Supply of cable joint, [fused   unfused]	each
67106	Supply of aerial cable strain clamp	each
67107	Supply of aerial cable connector, [type]	each
67108	Supply of right angle strain relief bushing (to suit 26 mm diameter hole)	each
67109	Installation, jointing and termination of underground road lighting cable, [cores]	m
67110	Installation, jointing and termination of traffic signal cable, [cores]	m
67111	Installation, jointing and termination of loop detector cable, [cores]	m
67112	Installation, jointing and termination of cable, [usage], [cores]	m
67113	Installation, jointing and termination of aerial road lighting cable, [cores]	m

Standard Item No.	Description	Unit of Measurement
67191	Removal of underground cable	m
67192	Removal of aerial cable	m

## 2.2 Work Operations

**Item 67101** Supply of underground road lighting cable, [*conductor size*], [*number of cores*] cores, [*core insulation*], [*sheath insulation*], [*conductor material*]

**Item 67102** Supply of aerial road lighting cable, [*conductor size*], [*number of cores*] cores, [*core insulation*], [*sheath insulation*], [*conductor material*]

**Item 67103** Supply of traffic signal cable, [*conductor size*], [*number of cores*] cores, [*core insulation*], [*sheath insulation*], [*conductor material*]

**Item 67104** Supply of cable, [*usage*], [*conductor size*], [*number of cores*] cores, [*core insulation*], [*sheath insulation*], [*conductor material*]

**Item 67105** Supply of cable joint, [*fused* | *unfused*]

**Item 67106** Supply of aerial cable strain clamp

**Item 67107** Supply of aerial cable connector, [*type*]

**Item 67108** Supply of right angle strain relief bushing (to suit 26 mm diameter hole)

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*, and
- b) supply of all materials to the Site.

**Item 67109** Installation, jointing and termination of underground road lighting cable, [*cores*]

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of cables through ducting
- c) connection and termination of cables
- d) replacement of draw ropes in ducting, and
- e) testing of installation.

**Item 67110** Installation, jointing and termination of traffic signal cable, [*cores*]

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of cables through ducting, posts, mast arms and poles
- c) connection and termination of cables, including the connection and termination of cables at the appropriate terminal assembly within the traffic signal post, mast arm or joint use pole
- d) replacement of draw ropes in ducting, and
- e) testing of installation.

**Item 67112 Installation, jointing and termination of cable, [usage], [cores]**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of cables
- c) connection and termination of cables, and
- d) testing of installation.

**Item 67113 Installation, jointing and termination of aerial road lighting cable, [cores]**

Work Operations incorporated in the above item include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) installation of cable
- c) connection and termination of cables, and
- d) testing of installation.

**Item 67191 Removal of underground cable**

**Item 67192 Removal of aerial cable**

Work Operations incorporated in the above items include:

- a) Work Operations listed in Clause 2.1.5 of MRS01 *Introduction to Specifications*
- b) de-energisation of circuit
- c) removal of cable, and
- d) transport to Transport and Main Roads' storage Site.

**2.3 Calculation of quantities**

Quantities for the supply and installation of underground cable for traffic signals (other than multicore) and road lighting cable shall be the sum of the measured duct length plus 4 m for each pit through which the cable passes.

Quantities for the supply and installation of traffic signal multicore cable shall be the sum of the measured duct length plus 12 m for each pit at controller, posts, joint-use poles and mast arm columns and 2 m at each intermediate pit through which cable passes plus 5 m from pit to terminal connection.

Quantities for the supply and installation of aerial cable shall be the sum of measured span lengths plus 2 m for each span, for each type of cable specified.

Superseded